

APPROVED LAND CORNER  
P.A. 345 OF 1990  
MIDLAND COUNTY

251

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

2/18/95

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T16N R2W	1-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MIDLAND COUNTY  
REMONUMENTATION & FILED

14 AUG 95 3:05 P.M.

BEVERLY J THAYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, PAUL B. LAPHAM, in a field survey on MAY, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1-5 CORNER COMMON TO SECTIONS 10, 11, 14 AND 15

- 1832 WRIGHT, SET POST, B. ASH 14" N65°E 12 LKS., HEMLOCK 10" S30°W, 13 LKS.
- 10-13-10 GIBBS, POST, OLD CORNER SET IN HWY. C.S.R. 294/95
- 2-14-74 LAPHAM, FOUND 1/2" BAR, L.C.R.C. #282
- 10-13-81 GILBERT, 1/2" RE-ROD W/CAP 22433
- 8-22-84 GILBERT, 1/2" ROD
- 9-27-84 LAPHAM, FOUND CAPPED IRON

WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee and is on file at the Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-5 CORNER COMMON TO SECTIONS 10, 11, 14 AND 15

Found 1/2"x18" capped iron over 15"x3/8" sq. boat spike per surveys by Lapham and Gilbert

Corner, 1-5 was approved for remonumentation at a Peer Review Committee Meeting on 7-18, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-5 Corner common to Sections 10, 11, 14 and 15

Set 5/8" x 36" re-rod with brass cap stamped "Midland Co. Remon. Cor. PS 9433". Accepted as best available evidence of the accepted position of the corner.

- N37°W, 61.20' - N&T IN 18" ASH
- N42°E, 80.60' - N&T IN POWER POLE
- S45°E, 66.25' - N&T IN TWIN 9" MAPLES (WEST TREE)
- S05°E, 52.15' - N&T IN TWIN 9" MAPLES (NORTH TREE)



Signed by Paul B. Lapham

Date 7-19-95

Surveyor's Michigan License No. 9433