

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

8/28/97

For corners in

MIDLAND (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>16N</u> R <u>2W</u>	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

350

STATE OF MICHIGAN
MIDLAND COUNTY
FILED 4
REMONUMENTATION
11 DEC 97 12:01 P.M.

BEVERLY J THAYER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on July 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1830 Wright
Wit.-Sugar tree 14 S43W 14 lks
Beech 6 N43E 32 lks
1916 Redman, C.S.R.
Wood Post & ? sleigh runner
Wit.-Apple tree 4" S52-40E, 141
North 42.02 to K-2
South 40.03 to K-3
7-11-72 Coutright (132) 1-158
No witnesses
North 2762.61 to K-1

3-08-73 Whittier, L.C.R.C. 205
Fd remains of 2" Sq. rotted wood stake
next to ?. Drove 3/4" pipe 20" long into
center of old wood stake (old wood stake
about ? deep).
Wit.-S85W 53.66 N&D in P.P.
S30E 88.77 N&D in 15" Maple
N40E 53.33 N&D in 8" Maple
In line with fence to East & 1.5' E at
centerline

11-10-77 Lapham, L.C.R.C. 437
Fd 1" Pipe
Wit.-East 25.05 F. Post
West 53.60 P.P.
N25E 53.38 Clump Maple
S45E 92.96 12" Apple Tree

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found very old 3/4" pipe; removed and found 1" x 3" sleigh runner 1 1/2 ft. deep on North side of pipe. Found 1916, 1973 and 1977 witnesses, stump remains of apple tree. Meas. North 2768.93 ft. (C.S.R. 2773.32) to K-1. Meas South 2641.30 (C.S.R. 2641.98) to K-3.

Corner, K-2 was approved for remonumentation at a Peer Review Committee Meeting on August 28, 1997.

SURVEY &
REMONUMENTATION

FEB 24 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 18" Gas Pipe with Brass Cap stamped "Midland Co. Remon. Cor. P.S. 27458" in Monument Box in place of old pipe. Accepted as perpetuation of old C.S.R. Corner.

Witnesses:
N28E 53.38', nail & tag, 24" Maple (OBT)
West 53.60', nail & tag, P.P.(OBT)
S40E 106.72' Center of 10" W. Pine in yard
N18W 165.36', nail & tag, P.P.
S53E 32.45' N. end 12" C.M.P.

SECTION

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-31-97

