

RATIFIED BY DEEDS BOOK  
 PA 342 OF 1995  
 MONROE COUNTY, MICHIGAN  
 date: 9/26/95  
 County Rep.: [Signature]

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Monroe (58)  
 (County)

Located In:  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T 58 R 7E  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Corner Code: H-12  
**SURVEY & REMONUMENTATION**  
APR 04 1996  
**COMMISSION**

RECEIVED FOR RECORD  
 95 DEC 29 AM 9:01  
 REGISTER OF DEEDS  
 MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**1995 REMONUMENTATION PROGRAM**

I, G.B. WARNKE, JR., in a field survey on Sept.-Oct., 1995, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Center of Section 34 Sections 31 & 32 / On Yensch Road - Tarby surface.  
 Not set by GLO Surveyor. 1939, witness card states stone found. M.R. Fleck - 1973 survey recorded in Liber 644, Page 965, notes use of corner with 2 witnesses (material for corner not noted) & 1976 survey notes R.R. Spk. 1974, K.L. Suydam survey states found iron with 2 witnesses. 1991, Andrus Survey states found railroad spike. 1993, G.B. Warnke recorded LCRC, Liber 3, Page 309, notes found railroad spike and replaced with 3/4" iron pipe.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

9/95, Found 3/4" iron pipe, based on field work and calculations - found iron is 6.85 feet north & 0.83 feet west of theoretical center of Section. 9/26/95, corner was Peer Group approved. 10/26/95, G.B. Warnke crew set 1" x 36" iron pipe with remonumentation cap in monument box to replace iron pipe.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 1" x 36" iron pipe with brass remonumentation cap in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Witnesses:  
 South 80° West 30.35 feet to found nail/shiner in east face of 12" Ash  
 North 15° East 116.88 feet to found nail/shiner in west face electric pole  
 South 85° East 21.53 feet to found chisled "" in top east end of concrete culvert  
 South 85° West 69.5 feet to found nail/shiner in north face 12" Ash  
 East 4.5 feet +/- in center of pavement

Signed by [Signature]  
 Surveyor's Michigan License No. 19474

Date Dec 19, 1995