

Surveyor's  
Registration Certificate

MAY 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

97 JAN 10 PM 2:06

For corners in  
MONROE (58)  
(County)

Located In: Corner Code #

1. Public Land Survey  
LONDON TWP.

T     R      
T     R      
T 58 R 7E             K-8

2. Property Controlling  
in Section

S     T     R      
S     T     R    

3. Miscellaneous  
Property in Sec.

S     T     R      
S     T     R    

REGISTER OF DEEDS  
MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

G.B. WARNKE, JR., in a field survey on 1995-1996, 19     do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1996 G.B. WARNKE CORNER

1/4 Corner to Sections 23 & 24

On Gramlick Road being gravel surface (1/2 mile S. of Allison Rd.)

A. Description of original monument and accessories and/or subsequent restoration:

1847, GLO Surveyor, Orange Risdon, set 1/4 Sec. post & witnesses: B Oak 12 S53°W 236 & B Oak 12 S87°W 155  
Oct. 1973, G.B. Warnke survey (#73-115) notes set axle shaft (1/2 the distance between K-9 & K-7 & 11.76 feet east of straight line based on stone at J-8 & existing fence lines in Sec. 23);  
G.B. Warnke recorded surveys, #71-01, L.697, Pg. 993, dated Jan. 1974 & #74-63, L.670, Pg.857, dated June 1974 & survey #76-81, dated June, 1976, note found axle shaft;  
1980, A.J. Marino field notes show found axle shaft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 1995, G.B. Warnke field crew attempted to locate axle rod and determined that rod was no longer in the area. Re-established axle rod position by same procedure used in setting axle rod, per G.B. Warnke survey 73-115 - [1/2 the distance between K-9 & K-7 & 11.76 feet east of straight line between corners] set 5/8 inch X 30 inch capped rebar. (Note: L.C.R.C. L.2, Pg.356 is recorded as K-7, T5S, R7E is in error the correct point is K-7, T5S, R8E)  
11/12/1996, corner was approved by Remonumentation Peer Group - reference corner dossier for further info.  
12/17/1996, set 1" x 36" iron pipe with brass remonumentation cap over existing 5/8" x 30" rebar and witnesses as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap over existing 5/8" x 30" rebar and is accepted as a careful and faithful reestablishment of the position of the original corner and witnesses:

- West 33.00 feet to found 3/4 inch capped iron pipe (#19474)
- South 30° West 107.55 feet to found nail/shiner in southeast face electric pole
- South 27° West 97.17 feet to set nail/shiner in easterly face twin 10 inch Oak tree
- North 20° West 186.35 feet to set nail/shiner in easterly face of 12 inch Cedar tree

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICH.  
date: 11/12/96  
County Rep.: [Signature]

Signed by [Signature]  
Surveyor's Michigan License No. \_\_\_\_\_

Date 12/26/1996

