

CLERK OF
 PUBLIC RECORDS
 MAY 8 1997
 MONROE COUNTY

RECORDED
 97 JUN 10 PM 2:11

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 MONROE COUNTY, MICH.

For corners in
Monroe (58)
 (County)

Located in: Corner Code #

1. Public Land Survey
 Exeter Twp.
 T 5S R 8E E-8

2. Property Controlling
 in Section
 S T R

3. Miscellaneous
 Property in Sec.
 S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, G.B. WARNKE, JR., in a field survey on 1995-1996, 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1995-1996 REMONUMENTATION PROGRAM
 1/4 Corner to Sections 20 & 21
 At Doty & Geiman Roads - gravel surface

- A. Description of original monument and accessories and/or subsequent restoration:
 1847, GLO Surveyor, Orange Ridson, set 1/4 cor. post - witnesses: W. Oak 12 N51E 90 lks & Poplar 2 S62W 4 lks.
 1800's, old survey book notes 1/4 post on W. sec. line - witness: Willow 24" S85E 51.
 1886, old survey book notes stone.
 A.J. Marino - 1961 field notes state P.I.
 M.R. Fleck - 1973 survey, recorded in Liber 650, Page 470, notes F.I.P. & survey, recorded in Liber 977, Page 556, notes found I.P. & 1979 survey notes F.I.P.
 1990, G.B. Warnke recorded LCRC, Liber 3, Page 100, to set auto valve over round top stone and witnessed other points in area.
 1992, J.C. Andrus recorded LCRC, Liber 3, Page 253, found I.P. from old Case & Fleck records.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10/95 - checked point being auto valve over stone and witnesses per LCRC, Liber 3, Page 100.
 10/24/1995, corner was approved by Remonumentation Peer Group - reference corner dossier for further info.
 12/17/1996, set 1" x 36" iron pipe with brass remonumentation cap to replace found auto valve over stone and witnesses as shown below.

RATED BY PEER GROUP
 FA 345 OF 390
 MONROE COUNTY, MICHIGAN
 date: 10/24/95
 County Rep.: [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 1" x 36" iron pipe with brass remonumentation cap & is accepted as the best available evidence of the position of the original corner & witnesses: South 32°47' East 3.66 feet to found 1/2" iron pipe with pinched bottom
 North 10°04' East 11.41 feet to fd. 1/2" i.pipe w/ pinched bottom & North 30°12' East 17.51 feet to fd. 1" i.pipe
 North 50° West 57.20 feet to nail in N'y face of telephone pole
 South 60° East 39.00 feet to nail in NE'y face of electric pole
 North 72° East 76.80 feet to NW'y corner of main foundation of house #11100
 North 83° East 73.21 feet to SW'y corner of main foundation of house #11100
 South 29° West 27.35 feet to 1 1/2 inch iron pipe in concrete at southerly edge of drive
 South 45° West 114.70 feet to northeast corner of attached garage foundation of house #11097

Signed by [Signature]
 Surveyor's Michigan License No.

Date 12/26/1996

