

date: 9/24/1995  
County Rep.: [Signature]

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Monroe (58)  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                       |  |   |
|---------------------------------------|--|---|
| 1. Public Land Survey<br>Exeter Twp.  | T _____ R _____<br>T <u>5S</u> R <u>8E</u><br>T _____ R _____<br>T _____ R _____ | _____ <u>F-9</u> _____<br>_____<br>_____            |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____<br>S _____ T _____ R _____                               | _____ <u>SURVEY &amp;<br/>REMONUMENTATION</u> _____ |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____<br>S _____ T _____ R _____                               | _____ _____   |

RECEIVED FOR RECORD  
95 DEC 29 AM 9:02  
REGISTER OF DEEDS  
MONROE COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

APR 04 1996

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

COMMISSION

1995 REMONUMENTATION PROGRAM

I, G.B. WARNKE, JR., in a field survey on Sept.-Oct., 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner common to Sections 21 & 28 / not on road  
1847, GLO Surveyor, Orange Risdon, set qr. Sec. post at aver. dist. - witnesses: Elm 10 S.74E. 12 lks & Elm 12 N.11W: 8 lks. Old survey book (surveyor & date?) notes B2-86, SW Cor. of SE1/4 Sec. 21 with 2 witnesses. 1886, old book at south 1/4 corner of Sec. 21 notes (surveyor?) stake. 1990, G.B. Warnke LCRC, Liber 3, Page 90, found old corner post - fence to east, west & north, which have been in place for excess of 50 years per area property owners. Set 1 1/4" iron pipe in center of old corner post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9/95 - Found 1 1/4" iron pipe in center of old corner post base. 9/26/95 - corner was Peer Group approved. 10/11/95 - G.B. Warnke crew set 1" x 36" iron pipe with brass cap inside 1 1/4" found iron pipe in center of old corner post base.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass cap inside found 1 1/4" iron pipe in center of old corner post base and is accepted as the best available evidence of the position of the original corner and witnesses:  
North 10° West 4.93 feet to found #16 nail in blaze in west face of 12" Ash  
North 15° East 21.80 feet to set nail in blaze in east face 4" Ash  
North 85° East 22.11 to set #16 nail in blaze in south face 12" Elm  
South 60° East 8.32 feet to found #16 nail in blaze in southwest face of 5" Elm

Signed by [Signature] Date 12/19/1995  
Surveyor's Michigan License No. 19474

