

date: 9/26/1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

County Rep. For corners in Monroe (58)

Located In: _____ Corner Code ≠ _____

- | | | |
|---------------------------------------|--|-------|
| 1. Public Land Survey
Exeter Twp. | T _____ R _____
T <u>5S</u> R <u>8E</u>
T _____ R _____
T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____
S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____
S _____ T _____ R _____ | _____ |

SURVEY & REMONUMENTATION
 Register of Deeds Stamp & File Number

RECEIVED FOR RECORDS
 95 DEC 29 AM 9:03
 REGISTER OF DEEDS
 MONROE COUNTY, MICH.

4. Lot No. _____, Recorded Plat APR 04 1996
 5. Private Claims _____

COMMISSION

1995 REMONUMENTATION PROGRAM

I, G.B. WARNKE, JR., in a field survey on July-Oct., 1995, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to Sections 21, 22, 27 & 28 / On Sumpter Road - 4" asphalt surface over 18" large stone & gravel over yellow sand.
 1847, GLO Surveyor, Orange Risdon, set post Cor. of Secs. 21, 22, 27 & 28 - witnesses: Beech 12 S.58E. 33 lks. & Sassafrass 7 N.62W. 33 lks. 1886 notes (surveyor?) show Tin & Stake at southeast corner of Sec. 21. Old notes (surveyor?) show B2 P86, Stone S.E. Cor. Sec. 21, W.O. 10 N.15 1/2 E 176 1/2 links & W.O. 10 N.85 1/2 E 158 links. A.J. Marino: 1961 notes show P.CAP. & 1965 notes show P. RR SPIKE & 1975 notes show FIR. 1990, G.B. Warnke survey (#90-226) shows Set 3/4" Capped (#19474) Iron Rod/Rebar Over R.R. Spike Over 1/2" Iron Pipe & referenced, also found 1/2" iron rod 1.5' east & 0.2 feet north.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

7/25/95 - Found 3/4" capped (#19474) iron rod/rebar at surface; dug a 20" x 32" hole; found 1/2" iron pipe at 15" deep; probed in all directions especially towards other iron rod (1.50 feet east & 0.20 feet north) but no further evidence was found. Set 1" x 36" iron pipe inside monument box to replace 3/4" capped iron rod/rebar. 9/26/1995 - corner was Peer Group approved. 10/11/95 - G.B. Warnke crew set brass remonumentation cap on previously set 1" x 36" iron pipe inside monument box to replace rod/rebar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap inside monument box and is accepted as the best available evidence of the position of the original corner and witnesses:
 North 25° East 110.65 feet to nail/shiner in west face of electric pole
 North 75° West 35.25 feet to set double nail/shiner in southeast face of telephone pole
 South 45° West 41.23 feet to found nail/washer in north face of guy pole
 South 30° West 59.80 feet to nail/washer in east face of 20 inch Sycamore

Signed by [Signature]
 Surveyor's Michigan License No. 19474

Date 12/19/1995

