MAY 29 1997

COMMISSION

REGISTER OF DEEDS

97 JAN 10 PM 2:05

REGISTER OF DEEDS MONROE COUNTY, MICH

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONROE (58)
(County)

Located in: Corner Code #

1. Public Land Survey — T___ R___ ___
   T___ R___ ___
   EXETER TWP. — T5S R 8E — I-4
   T___ R___ ___
2. Property Controlling — S___ T___ R___ ___
   in Section — S___ T___ R___ ___
3. Miscellaneous — S___ T___ R___ ___
   Property in Sec. — S___ T___ R___ ___

Register of Deeds Stamp & File Number

4. Lot No. _____ , Recorded Plat _____
5. Private Claims _____



I, G.B. WARNKE, JR., in a field survey on 1996, 19 ___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

GEORGE B. WARNKE, JR. - 1996 CORNER
1/4 Corner common to Sections 10 & 11
On Martinsville Road (gravel) - 1/2 mile south of Colf Road

A. Description of original monument and accessories and/or subsequent restoration:

1819, GLO Surveyor, J. Fletcher, Set qr. Sec. post - witnesses: B. Oak 11 N65E 6 lks & Hickory 10 N30E 8 lks
1886, W. Baldwin drawing shows "1/4 stone (Section 10) on E. Sec. line - Elm 12 N87W 57 & Lynn 10 N30E 75 1/2". Notes show "40.11 1/2 set 1/4 post at ave. dis. - witnesses same as drawing.
March 1886, W. Baldwin notes "found the 1/4 post on E. side of Sec. as identified by Buckley. New witnesses: W. Oak 10 S31W 61 1/2 & Elm 18 S21W 108."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4/30/96 - G.B. Warnke crew started at capped remon. cor. (I-3) and measured down, along Martinville Road, 2637.36 feet (39.96 ch. per 1886 survey by W. Baldin) & 2647.59 feet (40.11 1/2 ch. per Book 2 Pg. 111 in Case & Fleck records). Dug numerous holes & probed the bottom, using deflection per Baldwin, found a 2.5 foot x 1.0 foot black and gray granite stone, 3 feet deep at 2647.96 feet south of I-3. Set 1/2" x 24" rebar over high point, then set 1" x 18" capped iron pipe over rebar and witnesses as shown below. 9/24/96, Peer group approved corner as stone to be replaced by 1" iron pipe with remon. cap. 12/27/96, set 1" x 30" steel pipe with brass remonumentation cap over 15" 1/2" rebar and drove 1 3/8" x 12" iron pipe down over the 1" pipe and railroad spike is on west side being 15" deep and witnesses as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 30" steel pipe with brass remonumentation cap over 15" 1/2" rebar and drove 1 3/8" x 12" iron pipe down over the 1" pipe & is accepted as the best available evidence of the position of the original corner & witnesses:
South 40° East 49.57 feet to set nail & shiner in westerly face 6" tree
South 80° East 50.95 feet to set nail & shiner in northerly face 8" tree
South 80° East 21.78 feet to easterly end of 12" CMP} south 6 foot to centerline of 12" CMP
South 75° West 15.83 feet to westerly end of 12" CMP}
centerline of 20 foot gravel road - East 5 feet
6 foot North of the 12" CMP

RATIFIED BY PEER GROUP
PASSED
MONROE COUNTY, MICHIGAN
date: 12/24/96
County Rep.: [signature]

Signed by [signature]
Surveyor's Michigan License No. _____

Date 12/27/1996

STATE OF MICHIGAN
19474 GEORGE B. WARNKE, JR.
PROFESSIONAL SURVEYOR
No. 19474
LICENSED PROFESSIONAL SURVEYOR

G.B. WARNKE CORNER - 1996

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14,1975
REVISED JAN., 1983
REVISED OCT., 1995