

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in
MONROE (58)
(County)

Located In: EXETER TWP.
T 5 S R 8 E
 Corner Code # M-11

- | | | | | |
|---------------------------------------|---|---|---|-------|
| 1. Public Land Survey | S | T | R | _____ |
| 2. Property Controlling in Section | S | T | R | _____ |
| 3. Miscellaneous Property in Sec. | S | T | R | _____ |
| 4. Lot No. _____, Recorded Plat _____ | S | T | R | _____ |
| 5. Private Claims _____ | | | | _____ |

RECEIVED FOR RECORD
 99 DEC 30 AM 9:38
Handwritten Signature
 REGISTER OF DEEDS
 MONROE COUNTY, MICH.

1999 G.B. Warnke Private Remonumentation Corner

I, George B. Warnke, Jr., in a field survey on June - November, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 - G.L.O - Joseph Fletcher -
 80.00 / Set post cor. of Secs. 25 & 36
 W. Oak 24 S30W 64 lks. & Elm 20 N28E 36 lks.
 Wet Swampy Prairies & W. Oak Barrens
- 7/1956 - A. J. Marino - notes - P. Cap
- 3/1965 - A. J. Marino - notes - P. Spike
- 8/1972 - John Weithman - recorded (can't read Liber & Page) - rr spike fnd
- 5/1973 - M. R. Fleck - LCRC, Liber 1, Page 363 - found RR. Spike at intersection of centerlines of Zink & Exeter Roads
 N34°W 39.10 to nail in pole
 N50°E 45.65 to nail in post
 S21°E 82.52 to nail in pole
- 8/1974 - M. R. Fleck / Case & Fleck - Job #18697 - FD RR SPIKE
- 8/1976 - A. J. Marino - notes - R. RR. SPIKE
- 1985 - G. B. Warnke - Job #85-365 - Fd R.R. Spike
 South 0.12' Iron Rod
 N40°W 39.12' nail & washer in SE face elec. pole
 S30°E 49.72' NW cor. of barn foundation
 N45°E 45.60' nail (P.K.) in SW face wood post
 S40°W 37.18' nail & shiner in NE cor sq. wood post
- 8/1994 - G. B. Warnke - witness card - Fd Railroad Spike at Surface (witnesses match 1999 witnesses)
 N34°W 39.20' fd nail / washer SE face utility pole
 S21°E 82.52' fd PK nail NW face utility pole
 S30°W 119.48' fd nail / shiner E. face utility pole
 S80°W 37.20' fd nail /shiner NE corner RR tie

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located at intersection of Zink & Exeter roads / in asphalt pavement - 3" of asphalt over 8" of stone over black sand.
 6/1999 - Dug 24" x 24" hole & removed railroad spike that was at surface. Probed in all directions with nothing further found. Replaced RR spike with set 1" x 36" pipe in set monument box. 11/29/99 - set brass cap on pipe in box.

Handwritten Signature

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/12/1999, COUNTY REP. _____
 Corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1" x 36" pipe with set brass remonumentation cap in set monument box & Witnesses:
- North 34° West 39.20' found nail / washer in southeast face utility pole
- South 21° East 82.52' found PK nail in northwest face utility pole
- South 30° West 119.48' found nail / shiner in east face utility pole
- South 80° West 37.20' found nail / shiner in northeast corner railroad tie
- South 35° East 53.98' to double head nail & remon disc in east face of 30" Maple

Signed by *George B. Warnke, Jr.*
 Surveyor's Michigan License No. 19474



Date November 30, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1994