

**SURVEY & REMONUMENTATION**

APR 06 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Monroe Located In: Ash Twp. Corner Code #  
(County)

1. Public Land Survey T 5 S R 9 E 12  
T     R      
T     R      
T     R    

2. Property Controlling in Section S     T     R      
S     T     R    

3. Miscellaneous Property in Sec. S     T     R      
S     T     R    

RECEIVED FOR RECORD  
98 DEC 30 AM 8:31  
*Scott A. Warnke*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1									●				
2	6		5		4								1
3													
4	7		8		9			10		11			12
5													
6	16		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

I, Scott A. Warnke, in a field survey on August, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Private Remon. corner on Carter Road 2106.71 feet East of Briar Hill Road excavated for remonumentation program.

A. Description of original monument and accessories and/or subsequent restoration:  
1820 G.L.O. set post at the average distance of 40.06 chains. W.Ash 10", S 65° E, 38 Links; W.Oak 12", S 5° W, 33 Links.  
1945 A.J. Marino survey uses corner, material and witnesses not given.  
1958 A.J. Marino found stone.  
1965 Marino found stone. Witnesses: S.W. 24.75 to old post. S.W. 27.1' to old post.  
1967 A.J. Marino found stone.  
1979 J.A. Fish uses corner, material and witnesses not given.  
1980 Marino found 3/4" I.P. He set three hubs for witnesses.  
1990 G.B. Warnke, Jr. found 1/2" iron pipe 7" deep. Excavated under iron and found no other evidence. Set Railroad spike.  
1991 G.B. Warnke, Jr. Found stone.  
Witnesses: South 1.06' to 3/4" iron pipe (previously recorded as corner.)  
WNW 117.35' nail/shiner in S. face of elec. pole.  
ENE 163.35' nail/shiner in W. face of elec. pole.  
West 2106.8' to 5/8" iron rod at intersection of centerlines of Briar Hill Road with Carter Road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found Stone. Excavated hole around stone 3'x3' by 3' deep. Stone was a large granite stone which was 1.8' high, 0.5' diameter at top and 1.5' diameter at bottom. Removed stone in pieces but found nothing under stone.  
Set 1" x 36" iron pipe at location of High point of stone and set pieces of the granite stone around the base of the 1" iron pipe.

RATIFIED BY PEER GROUP, P.A. 345 OF 1990, MONROE COUNTY, MICHIGAN; DATE 12/8/98 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 1" x 36" iron pipe with brass remonumentation disk 6" below gravel road surface.  
Witnesses: N 80° W, 117.33 feet to nail & shiner in South face of power pole.  
West, 2106.71 feet to found 5/8" iron rebar at intersection of Carter Road and Briar Hill Road.  
N 45° W, 167.75 feet to concrete nail & shiner in NE face of power pole.  
N 80° E, 163.96 feet to nail & shiner in West face of power pole.  
South, 32.29 feet to "MAG" nail with bottle cap in West face of 3" Hickory tree.

Signed by Scott A. Warnke  
Surveyor's Michigan License No. 41913

Date 12-28-98

