

REMONUMENTATION

APR 28 1995

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 11/8/1994  
County Rep.: [Signature]

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
94 DEC 16 PM 3:20

[Signature]  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

For corners in

MONROE

(County)

Located In: ASH TWP. Corner Code ##

- 1. Public Land Survey T 5 S R 9 E L-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

**1994 MONROE COUNTY REMONUMENTATION PROGRAM**

Peer Group approved corner on 11/8/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 11/15/1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-7, T5S, R9E, Ash Township, Monroe County - ID No. 58 South 1/4 Corner Common to Sections 13 and 24 (Ready Road, 1/2 mile west of Berlin Road - 1/2 inch tarby over 8 inch stone)  
1817 G.L.O. Surveyor Joseph Fletcher set 1/4 corner at 6 inch Hickory at corner. 1903 L.A. Howard found stone witnessed: Red maple 8 inch S.20 1/3°W. 1.06 3/4 chains, Sugar Maple 8 inch S.59°W. .84 chains. 1968, A.J. Marino notes found iron rod. 1974, Gary Stanley recorded L.C.R.C., Liber 2, Page 43, found iron pipe. Surveys by various surveyors used an iron rod. Review of Ready Road road survey revealed location of stone excavated which fit L.A. Howard survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 - 10/94, found 1/2 inch iron pipe at surface, dug a 18 inch X 20 inch hole found a stone 13 inches deep, removed the stone, found no post. Set a 1 inch X 36 inch iron pipe in monument box to replace stone and found iron pipe and witnessed as shown below. 11/15/94, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 - Set 1 inch X 36 inch iron pipe with brass remonumentation cap in monument box to replace stone and iron pipe and is accepted as the best available evidence of the position of the original corner and  
Witnesses:  
South 40° West 54.40 feet to found P.K. in northwest side of 36 inch Maple  
North 45° West 3.35 feet to a 1/2 inch iron rod  
North 35.28 feet to found P.K. nail in west side utility pole  
North 5° West 35.68 feet to found capped iron pipe No.16031  
South 5° East 98.40 feet to northwest corner of residence No. 3530

Signed by [Signature] Date 11/15/1994  
Surveyor's Michigan License No. 19474

