

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC -9 PM 12:46

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 11-8-94
County Rep.: [Signature]

For corners in
MONROE
(County)

Located In: ASH TWP. Corner Code #

1. Public Land Survey	T <u>5</u> S R <u>9</u> E	<u>L-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Keri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims
1994 MONROE COUNTY REMONUMENTATION PROGRAM
Peer Group approved corner on 11/8/1994 per Act 345 of 1990.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, G.B. WARNKE, JR., in a field survey on 11/15/1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11, T5S, R9E, Ash Township, Monroe County - ID No. 58
1/4 Corner Common to Sections 25 & 36 (On Labo Road - hard surface)
July 1817, G.L.O. Surveyor, Joseph Fletcher, west 40.05 chains in line between Sections 25 & 36 and set 1/4 post - witnesses: Elm 9 inch South 11 links & B. Ash 12 inch S.63°W. 22 links. 1973, L.C.R.C., Liber 1, Page 339, found 1/2 inch iron pipe. 1991, L.C.R.C., Liber 3, Page 178, by G.B. Warnke to found 1/2 inch rebar - 1962 witness to school fits. 1924 & 1950, Case & Fleck survey used iron pipe at 1/4 corner. 1978, A.J. Marino notes F.I.P. 1962, M.D.O.T. surveyor, Ray Graf, 5/8 inch iron with witness to brick school. 1973, notes a 1/2 inch iron pipe. 1992, L.C.R.C., Liber 3, Page 192, by G.B. Warnke to found 1/2 inch rebar.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 - Found 1/2 inch rebar and witnessed as shown below. 11/15/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace rebar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace rebar and is accepted as the best available evidence of the position of the original corner and Witnesses:
North 53° West 97.62 feet to southeast corner of brick school building
North 70° West 80.24 feet to set nail/shiner in east side of 24 inch Elm
North 60° East 83.30 feet to set nail/shiner in south side of siren pole
South 45° East 44.13 feet to set nail/shiner in west side of electric pole



Signed by [Signature]
Surveyor's Michigan License No. 19474

Date 11/15/1994