

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC -9 PH12:45

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 10-4-94
County Rep.: [Signature]

For corners in

MONROE
(County)

Located In: ASH TWP. Corner Code #

1. Public Land Survey	T <u>5</u> S R <u>9</u> E	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 10/4/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 11/15/1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-6, T5S, R9E, Ash Township, Monroe County - TD No. 58 (not common to A-6, T5S, R10E)
East 1/4 Corner Section 13 on Township line (Berlin Road, 1/2 mile north of Ready Road - gravel surface)
1817, GLO Surveyor, Joseph Fletcher, ran south on the east boundary of Section 13 at 40.00 chains, set qr. Sec. post: Sugar 12 (inch) S.50°E. 82 (links) & Sugar 12 (inch) N.27°W. 27 (links). 1903, L.A. Howard notes "stone found, misplaced, set it right in line & equal distant between section corners, said to have been out & lay in ditch & no one knows who replaced it". 1949, Road Commission found stone. 1958, A.J. Marino found stone. 1972, Gary A. Stanley set iron pipe, survey recorded in Liber 631, Page 107. 1975, A.J. Marino notes F.I.P. 1987, James Andrus notes found existing pipe, survey recorded in Liber 1002, Page 0807. 1990, Peter Palczynski found iron pipe. 1991, G.B. Warnke found 1/2 inch iron pipe over stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-6 - Found 1/2 inch iron pipe over stone and witnessed as shown below. 11/15/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap to replace 1/2 inch iron pipe over stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap to replace 1/2 inch iron pipe over stone and is accepted as the best available evidence of the position of the original corner and Witnesses:
North 15° West 94.37 feet to nail/shiner in east side of 4 inch Sycamore
South 5° West 7.64 feet to 1/2 inch iron pipe set as corner by G. Stanley
South 50° East 90.15 feet to northwest corner of residence No. 12500
North 85° East 148.00 feet to northwest corner of block building

igned by [Signature]
urveyor's Michigan License No. 19474

Date 11/15/1994

