

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

RECEIVED FOR RECORD

94 DEC -9 PM 12:47

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Peri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 11-8-94
County Rep.: [Signature]

For corners in

MONROE
(County)

Located In: ASH TWP. Corner Code ##

- | | | | | | | | |
|------------------------------------|---|---|---|---|---|---|------|
| 1. Public Land Survey | T | 5 | S | R | 9 | E | M-11 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 11/8/1994 per Act 345 of 1990.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **G.B. WARNKE, JR.**, in a field survey on 11/15/1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11, T5S, R9E, Ash Township, Monroe County - ID No. 58 (not common to A-11, T5S, R10E)
Section Corner Common to Sections 25 & 36 (Labo Road - soft surface)
1817, G.L.O. Surveyor, Joseph Fletcher, surveyed east line of Section 25 and set post at corner of Sections 25 & 36 - witnesses: Sugar 10 (inch) S.52°W. 15 (links) & Beech 6 (inch) N.65°W. 27 (links). 1973, found stone noted on maps. Old small book in G.B. Warnke's files notes stone witnessed at southeast corner of Section 25, T5S, R9E, (surveyor?). 1973, L.C.R.C., Liber 1, Page 339, by Art Crossman notes found stone. 1991 & 1992, L.C.R.C.'s, Liber 3, Page 177, and Liber 3, Page 193, by George B. Warnke to PK nail in stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 - Found PK nail in stone and witnessed as shown below. 11/15/1994, set 1 inch x 36 inch iron pipe with brass remonumentation cap to replace PK nail in stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap to replace PK nail in stone and is accepted as the best available evidence of the position of the original corner and Witnesses:
South 85° West 96.20 feet to set chisled "x" in top southeast corner of bridge abutment
South 45° East 45.56 feet to set nail in west face of 10 inch electric pole
South 48.30 feet to found nail in west face of electric pole
North 8.47 feet to 1 inch iron pipe at northwest corner of Section 31, T5S, R10E



Signed by [Signature]
Surveyor's Michigan License No. 19474

Date 11/15/1994