

- | N | S     |  |
|---|-------|--|
| 7 | 0     | Found stone, set Brass Section Cor. on 1" pipe, 6" below road surface. N18W, 23.39', 18" alm, hor. sp.; S78°45'W, 108.85', telephone pole, horiz. sp.; N78°E, 108.68', tel. pole, hor. sp.; N3W, 19.39', fence post, horiz. sp.; (W.L.P. 2/57)                               |
| 8 | 0     | Found old square stake, set Brass Sec. Cor. on 1" pipe 5" below road. S85°30'E, 20.31', 18" alm, hor. sp.; S50°30'W, 34.86', 2" road sign pipe, N68W, 43.18', 36" elm, SW side, horiz. spike. Nest on <del>Route</del> Rd. 170.3 to E. Edge conc. bridge deck. (W.L.P. 2/57) |
| 8 | 1     | Found rock, set brass sec. cor. on 1" pipe 4" below road. N41W, 32.34', 2" road sign pipe; N49E, 25.75', N. gate post, 3" iron pipe; N42°30'E, 20.20', S. gate post, 3" iron pipe. (W.L.P. 9/57)   |
| 8 | 1 1/2 | Found stone & old stake, set 3/4" x 30" iron pipe, 4 1/2" below road.  |
| 8 | 2     | Found 1/2" iron pipe & roads. N69°15'W, 49.18', 24" maple, horiz. spike; S35°30'W, 35.29', road sign pipe. N0°45'E, 19.66', steel fence post 8" high; S28°30'E, 44.36', 10" box elder tree. (W.L.P. 9/57)  |