

REMONUMENTATION

APR 28 1995

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED FOR RECORD

94 DEC 29 AM 10:59

date: 10-26-94
County Rep.: [Signature]
For corners in

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

MONROE (County)	Located In:	Corner Code #
	BERLIN TWP.	
1. Public Land Survey	T 5 S R 10 E	A-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 10/25/1994 per Act. 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 10/26/1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6, T5S, R10E, Berlin Township, Monroe County - ID No. 58 (not common to M-6, T5S, R10E)
West 1/4 Corner Section 18 on Township line
(Berlin Road, 1/2 mile north of Ready Road - 6" stone over clay)
This corner was not set in Joseph Fletcher's 1817 survey for GLO. 1949, Road Commission found stone. 1969, A.J. Marino found stone. 1972, Gary Stanley found stone, survey recorded in Liber 631, Page 107 and recorded L.C.R.C. Liber 2, Page 62, June 4th, 1975. 1979, G.B. Warnke found stone. 1990, Peter Paul Palczynski found stone. 1991 and 1992, G.B. Warnke found stone and recorded set 3 1/2 inch bolt over stone with 1 1/4 inch steel balls on north and south sides in L.C.R.C., Liber 3, Page 235.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 - On line between M-6 & M-7, T5S, R9E, set 1 inch X 36 inch pipe 1.35 feet to east of the center of found stone as correction corner to said stone, 4 inches deep using witnesses on L.C.R.C., L.2, Pg 62, used in survey in Section 13 and witnessed as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 - Set 1 inch X 36 inch iron pipe with brass remonumentation cap 1.35 feet east of center of stone; and, this position not established by original government surveyors and this monument is accepted as the best available evidence of the position of the corner; and, Witnesses:
East 22.90 feet to West face of 2 inch diameter steel post
East 31.65 feet to iron pipe
South 35° East 104.25 feet to double headed nail in west face of 14 inch Apple tree
North 40° East 41.48 feet to double headed nail in West face of 6 inch Hickory or Ash tree
South 40° West 55.34 feet nail in east face of 5 inch Sycamore tree

Signed by [Signature] Date 10/26/1994
Surveyor's Michigan License No. 19474

