

REMONUMENTATION

APR 28 1995

COMMISSION

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 29 11:10:59

Eric Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

date: 11/8/1994

County Rep.: *ABC*

For corners in
MONROE
(County)

Located In: BERLIN TWP.
Corner Code #:

1. Public Land Survey	T 5 S R 10 E	A-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 11/8/1994 per Act 345 of 1990.

G. B. WARNKE, JR. in a field survey on 11/15/1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-11, T5S, R10E, Berlin Township, Monroe County - ID No. 58
Corner Common to Sections 30 and 31 on Township line (Labo Road)
1817, G.L.O. Surveyor Joseph Fletcher intersected west boundary 13 links north of post. Set post for Sections 30 and 31 and witnessed: Beech 10 inch North 36° East 13 links, W. Oak 40 inch South 61° East 30 links. Detroit Edison witnessed iron pipe. 1966, A.J. Marino notes a 3/4 inch iron pipe 8.58 feet (.13 X 66 chains = 8.58 feet) north of stone - M-11, T5S, R9E. 1973, Art C. Crossman recorded found iron pipe in L.C.R.C., Liber 1, Page 335.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 - Iron pipe and witnessed as shown below. 11/15/1994 - set 1 inch x 36 inch iron pipe with brass remonumentation cap to replace the iron pipe. Corner observed along range line for closing corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap to replace the iron pipe and is accepted as the best available evidence of the position of the original corner and Witnesses:
South 8.58 feet to found brass remonumentation cap for M-11, T5S, R9E, Ash Twp.
South 80° West 56.81 feet to found "x" on southeast corner of bridge abutment
South 40° East 52.27 feet to found nail/shiner in west face of electric pole
South 97.80 feet to found double head nail in west face of electric pole

Signed by *[Signature]*
Surveyor's Michigan License No. 19474

Date 11/15/1994

