

MAR 19 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

SECTION

For corners in

MONROE (58)
(County)

Located In:

Corner Code #

BERLIN TWP.

T5S R10E

D-5

- 1. Public Land Survey _____
- 2. Property Controlling in Section _____
- 3. Miscellaneous Property in Sec. _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED FOR RECORD
99 SEP 30 AM 9:01
Lester Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

1998 & 1999 G.B. Warnke Remonumentation Private Corner

I, George B. Warnke, Jr., in a field survey on July, 1998 & August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 - GLO - Joseph Fletcher - West on the true line between Secs. No. 8 & 17 - 39.50 set the 1/4 sec. post at average dis. from which a Beech 10 ins. dia. bears N24E 20 lks. dis. & a Beech 6 ins. dia. bears N4E 10 lks. dis. - 79.00 Section corner late 1800's to early 1900' - surveyor? - notes in small old books at Warnke's office - stone
- 1976 - Roskelly, Jakobson & Assoc. - Survey #76-1-41 recorded in Liber 703, Page 374 - N1/4 Cor. Sec. 17 Fd. Iron Bar - no witnesses stated or shown
- 1988 - G.B. Warnke - Survey #88-249 - Found Stone - witnesses:
West 12.10' nail N. side 40" Oak
South 4.30' nail E. side 10" Beech
East 18.36' nail S. side 15" Oak
North 0.45' steel fence post
- 1989 - G.B. Warnke - LCRC, Liber 3, Page 65 - Found stone - witnesses match 1988 G.B. Warnke #88-249
- 1998 - G.B. Warnke - Survey #98-0040 - Found granite stone 1' diameter - witnesses reference LCRC, Liber 3, Page 65

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is in field / woods being +/- 1300' north of Carleton - Rockwood Road
8/30/99 - excavated found 12" diameter granite stone, no further evidence found, and replaced stone with 1" x 36" iron pipe with brass remonumentation cap.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 9/29/1998, COUNTY REP. *[Signature]*

and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with set brass remonumentation cap to replace found stone & Witnesses:
West 12.10 feet to nail in north side of 40" Oak
South 4.30 feet to nail in east side of 10" Beech
East 18.36 feet to nail in south side of 15" Oak
North 0.45 feet to steel fence post
North 0.80 feet to remon carsonite survey marker



Signed by *[Signature]*
Surveyor's Michigan License No. 19474

Date August 12, 1999