

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in


Wayne (County) Located In: City of Rockwood Corner Code # G-4
1. Public Land Survey T 5 S R 10 E
2. Property Controlling in Section S
3. Miscellaneous Property in Sec. S

Liber-30864 Page-24
99595875 12/30/1999
F.E. Yountblood, Wayne Co. Register of Deeds

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-8-99
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Michael S. Hoben, in a field survey on Sept. 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:



NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Monument Description, Location, Name, and Status. Includes entries for 1817 GLO Notes, 1920's WPA, 1922 'Rockwood Gardens', 1925 'Stuart & Hurst's Rockwood Sub.', and 1933 'Assessor's Rockwood Plat No. 4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 I found a 1" pipe (top mushroomed) in a north/south tree row, 205' +/- East of the NE corner of asphalt parking lot of the 'Rockwood First Congregational Church. WPA found two corners in this area; I couldn't find a second corner. This corner is close to a split that was set by GLO. This point is the W1/4 cor found by the WPA. No previous witnesses remain. Lot 116 of Assessor's Plat No. 4 agrees with found G-4 SW corner of Lot 36 agrees with found G-4

Distance to G-3 = 2634.62' (GLO = 2640')(WPA = 2634.20')
Distance to G-5 = 2628.67' (GLO = 2640')(WPA = 2628.68')


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 I replaced the 1" pipe with a 4"x 36" concrete monument with a 2" aluminum cap stamped "Wayne County Monument MI Act 345 #35994"

Table with 3 columns: Direction/Distance, Monument Description, and Material. Includes entries for S 35° E 14.86', S 24° W 27.23', West 45.26', and N 5° E 94.00'.

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

SECTION



Signed by Michael S. Hoben

Date Dec. 27, 1999

Surveyor's Michigan License No. 35994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1999

R LCR 9 4R 1 pg A. J.P. 2