



MAR 09 2000

## SECTION

CONTINUED FROM SECTION A ON PAGE 1 OF 2

- 5/1976, A.J. Marino – field notes – N.1/4 cor. Sec. 3 / H-1, T6S, R10E – (brass plate in concrete) Found State Land Marker – shows E'ly 2650.55 Rec. / 2650.462' Meas. to NE Cor. Sec. 3 / State Land Marker / I-1, T6S, R10E
- 1977, Fred Ayers – LCRC, Liber 2, Page 227 – H-13 / Found State of Michigan monument – chiseled cross in brass plate set in concrete post – witnesses:  
 North 36.53 ft. from nail in East side 6" tree  
 N44°E 108.83 ft. from nail (nail) in North side of utility pole  
 S12°E 41.42 ft. from nail in South side of 24" tree
- 10/1992 & rev. 2/1994 – Danny Bongiovanni / Midwestern Consulting - Job #9118 – N1/4 Cor Sec. 3, T6S, R10E (H-1) – F.I.P. / Found 3/4" Iron Pipe – witnesses:  
 Spike W/side 28" Oak N10°W 42.58'  
 Found Iron Pipe Due south 32.96'  
 NW corner Guard shack S35°E 155.67'  
 Found Iron Pipe S25°W 2.53'
- 2/1994, Patrick Hastings (Midwestern Consulting) LCRC, ~~(recorded?)~~ – H-13, T5S, R10E –  
 [LCRC Sec B] F-3/4" I.P.  
 Nail South Side 18" Oak N10°W 41.4' [GBW note – closely compared to Fred Ayres Survey #15994 quoted in Hastings Sec A]  
 Note: Found Iron Rod S25°W 2.53' from 3/4" I.P.  
 [LCRC Sec C] 3/4" I.P.  
 Set Spike W/side 28" Oak N10°W 42.58'  
 FIP Due South 32.96'  
 NW Corner Guard Shack S35°E 155.67'  
 Found Iron Rod S25°W 2.53'
- 2/1996, Patrick Hastings / Midwestern Consulting – Job #96031 – (H-13) S 1/4 cor. Section 34, T5S, R10E  
 FIP 15" below grade / Set 3/4" x 18" I.P. – witnesses:  
 FIP North 33.00'  
 NW cor. guard shack S35°E 155.67'  
 FIP S25°W 2.53'  
 FIP South 32.96'
- 1997 – Daniel J. Sandomierski – LCRC, Liber 4, Page 255 – found a 1/2" iron pipe with PVC cap #15411 in west bound lane of Reaume Road approximately 1/2 mile west of Robert Road – only reference to past information is LCRC, Liber 3, Page 335 – witnesses:  
 N18°05'W 42.48' set PK nail above recessed nail on west face of 28" Oak  
 S30°06'E 155.67' northwest corner to concrete foundation of a frame guard shack  
 S07°14'E 37.29' chiseled "x" on northwest face of the 5<sup>th</sup> fence post west of the corner post of a 7' cyclone fence  
 S27°13'W 2.61' found monument under asphalt road surface
- 7-9/1998 – G.B. Warnke requested information from surveyors in area with GBW mailings & with Peer Group notices

LIBER 3, PAGE 335