

SURVEY & REMONUMENTATION

DEC 0 2 1993

RC 1091

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 26951 PA 712

For corners in

Wayne (County)	Located In:	Corner Code -#
1. Public Land Survey	T <u>5S</u> R <u>10E</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 10-28-93 P.L.
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1091

I, Bruce Antcliff, in a field survey on August 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3									●			
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post
WPA (1930's) - Iron
Rec. Survey (1976) - Steel Rod in Iron Pipe
LCRC (1976) - Conc. Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Conc. Mon.; Measured to N1/4 S.11, W1/4 S.11 & N1/4 S.10 - All except to W1/4 S.11 check well with WPA & Rec. Surveys; to W1/4 S.11 is 10'± short of WPA but checks well with Liparoto Estates Sub. No. 1

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Wayne County Remonumentation Marker and Cap #25826 on Existing Monument

Witnesses

- Top Cen. Fire Hydrant, NE, 47.86'
- P.K. Nail N. Side (New) P.P., SE, 135.63'
- P.K. Nail SW'y side of 20" tree, WNW, 135.10'
- P.K. Nail SW'y side of twin 10" tree (W. tree), NW, 43.73'
- P.K. Nail W. side 10" twin tree (W. tree), NNW, 28.31'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff

Date 11-10-93

Surveyor's Michigan License No. 25826



FOREST COUNTY REGISTER OF DEEDS
 9310V 10 PM 2:15