

RATIFIED BY PEER GROUP
PA 345 OF 1890
MONROE COUNTY, MICHIGAN

date: 11/28/95

County Rep.: [Signature]
For corners in
Monroe (58)
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
05 DEC 29 AM 9:04

Located In:	Corner Code #
1. Public Land Survey DUNDEE Twp.	T <u>6S</u> R <u>7E</u> A-5
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>

SURVEY & REMONUMENTATION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____ **APR 04 1996**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1995 REMONUMENTATION PROGRAM

COMMISSION

I, G.B. WARNKE, JR., in a field survey on Nov.-Dec., 1995, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section Corner common to Sections 7 & 18 / On Rogers Road (east of Dundee - Azalia Road) - stone / gravel surface. (not common to M-5, T6S, R6E)
1819 or 1829, GLO Surveyor, J. Fletcher or Robert Clark, Jr., set post at intersection cor. of secs. 7 & 18 - witnesses: B. Ash 8 S.15E. 31 lks. & Hickory 28 N.87E. 20 lks. 1986, G.B. Warnke, survey #86-229, recorded in Liber 987, Page 187, notes PILE OF STONES. 1990, G.B. Warnke recorded LCRC, Liber 3, Page 143, to FOUND STONE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11/10/95 - G.B. Warnke crew found stone and checked witnesses. 11/28/95 - corner was Peer Group approved. 12/7/95 - replaced stone with 1" x 36" iron pipe with brass remonumentation cap and set stone and rocks next to iron and witnessed as shown below.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap and is accepted as the best available evidence of the position of the original corner and witnesses:
South 01° 30' West 34.60 feet to found pinched iron for northeast corner of Sec. 13, T6S, R6E (M-5)
South 12.5 feet to northerly edge of gravel road
South 05° West 20.34 feet to iron pipe in centerline of Rogers Road (gravel)
North 85° West 42.64 feet to car coin & nail (3 feet above ground) in southerly face of electric pole
South 87°04' West 440.59 feet to found 1/2" (I.D.) iron pipe (2" below asphalt pavement) at centerline of Dundee-Azalia Road & Rogers Road

Signed by [Signature] Date 12/19/1995
Surveyor's Michigan License No. 19474

⑧ A-5 TWS, R7E, DUNDEE TWP