

RATIFIED BY ACT PA 345 OF 1990
 MONROE COUNTY, MICHIGAN

date: 8/29/95
 County Rep.: [Signature]

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Monroe Located In: Corner Code #
 (County)

1. Public Land Survey T__ R__
 Raisinville Twp. T6S R7E I-11

2. Property Controlling S__ T__ R__
 in Section S__ T__ R__ SURVEY &
 3. Miscellaneous S__ T__ R__
 Property in Sec. S__ T__ R__ REMONUMENTATION

RECEIVED FOR RECORD
 95 DEC 28 AM 9:00
 REGISTER OF DEEDS
 MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

APR 04 1996

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____ COMMISSION

G.B. Warnke & Monroe Co. Road Commission Corner
 Bruce Antcliff 12/22 95
 I, G.B. Warnke, in a field survey on 3/10, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

I-11, Dunbar Road, Asphalt Pavement
 1819, GLO Surveyor Joseph Fletcher, set post corner at Sections 26, 27, 34 & 35, W. Oak 20 inches South 66° West 1.16 links; W. Oak 12 inches North 29° West 62 links. 1849, GLO resurvey by Orange Risdon found corner. 1948, C.J. Lisde of the Michigan State Highway Dept. Found a wedge shaped stone. 1967, A.J. Marino fieldnotes show railroad spike at corner, 1971 set iron at corner, 1979 found iron. 1993, G.B. Warnke found bent iron rod and replaced with 3/4 inch iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/10/95, found a 3/4 inch iron pipe, witnesses fit G.B. Warnke's witnesses of 1993, also pipe at corner fits distances from irons found per A.J. Marino's surveys of 1967 & 1979.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace found pipe and is accepted as the best available evidence of the position of the original corner.

Witnesses:
 North 5° West 27.59 feet to chiseled + in top east end of 12" concrete culvert.
 North 45° West 38.88 feet to chiseled + in top west end of 12" concrete culvert.
 East 1039.85 feet to center of monument box at centerline Lewis Ave.
 North 89°49' West 2637.43 feet to found 1/2 inch iron rod at north 1/4 corner of Section 34 (H-11).



Signed by Bruce Antcliff
 Surveyor's Michigan License No. 25826

Date 12-27-95

(12) I-11, T6S, R7E
 RAISINVILLE