

REMONUMENTATION

NOV 02 2000

LAND CORNER RECORDATION CERTIFICATE RECEIVED FOR RECORD
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 27 PM 2:24

For corners in SECTION
MONROE

Located In: Corner Code: #

G.B. Warnke - 1996 Corner

1. Public Land Survey	T	_____	R	_____	_____
	T	_____	R	_____	_____
FRENCHTOWN TOWNSHIP	T6S	9E	9E	B-3	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Eric Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner to Sections 6 & 7
On Reinhardt's Road in asphalt pavement

G.B. WARNKE, JR. in a field survey on 1995-1996, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	•											
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1847, G.L.O. Surveyor, Orange Risdon, set quarter Section post - witnesses: B. Oak 9" S18°W 43 links & B. Oak 10" N38°W 31 links.
April 1885, Willie Baldwin survey shows stone.
Old R.R. map, date unknown shows track going over area of corner, no monumentation mentioned on map.
1963, A.J. Marion set R.R. spike in line with fence, to east and west, from 1963 to 1982, notes call for R.R. spike found.
1967, Detroit Edison field notes by Malay, found R.R. spike.
1984 & 1989, G.B. Warnke found R.R. spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

March 31, 1995, found R.R. spike at surface of Reinhardt Road which check with witnesses of A.J. Marino's field notes of 1973 & 1976, also checks with witnesses of G.B. Warnke's surveys of 1984 & 1989.
4/9/1996, corner was approved by Remonumentation Peer Group.
10/16/1996, set 1" x 36" iron pipe with brass remonumentation cap in monument box to replace R.R. spike.

Had found R.R. spike at surface 20" diameter x 20" deep. Cedar poles (telephone or electric ?) 11-12" deep lying northeasterly to southwesterly. Westerly pole was about 2" from center of spike. Also, found boat spike 10" in hole in area of spike location. Piece of railroad rail is in bottom of hole about 18" deep. Dropped boat spike down new pipe. Lain R.R. spike on northerly side of pipe at about 12" deep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap in monument box to replace found R.R. spike and is accepted as the best available evidence of the position of the original corner and witnessed:
North 40° East 50.65 feet to a set nail/tag in southerly face of a 24 inch Maple
East 26.74 feet to found nail/washer in southwesterly face of wood post (could be remains of cut off telephone pole)
North 60° West 24.0 feet to southerly end of 12 inch concrete culvert
North 30° West 36.6 feet to northerly end of 12 inch concrete culvert

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY / MICHIGAN
date: 4/9/96
County Rep.: *[Signature]*

Signed by *[Signature]*
Surveyor's Michigan License No. 19474



12/4/1996

G.B. WARNKE 1996 CORNER / 95-0025

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983