

REMONUMENTATION

JUL 21 1997

COMMISSION

REGISTERED FOR...

97 JUL 10 PM 2:03

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONROE (58)

(County)

Located In:

Corner Code #

1. Public Land Survey

T___ R___

T___ R___

FRENCHTOWN TWP.

T6S R 9E B-4

T___ R___

2. Property Controlling in Section

S___ T___ R___

S___ T___ R___

3. Miscellaneous Property in Sec.

S___ T___ R___

S___ T___ R___

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

Grid table with columns A-L and rows 1-13. Cell (4,7) contains '7'.

I, G.B. WARNKE, JR. in a field survey on 1995-1996, 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1996 G.B. WARNKE CORNER
Center of Section 7, T6S, R9E

A. Description of original monument and accessories and/or subsequent restoration:

Center of Sections were not set during G.L.O. surveying.
1953, A.J. Marino cap was set in line with fences to east and west (bolt was found 4.3 feet north of fences).
1967, Detroit Edison survey by Malay set iron.
1976 and 1982, A.J. Marino surveys found iron rod.
1984, 1989 and 1992, G.B. Warnke surveys found iron rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

March 21, 1995 found 1/2 inch iron rod at surface of Reinhardt Road. Witnesses match A.J. Marino's 1976 witnesses and G.B. Warnke's witnesses of 1984, 1989 and 1992 surveys.
4/9/1996, corner approved by Remonumentation Peer Group.
10/16/96, Warnke crew set 1" x 36" iron pipe with brass remonumentation cap in monument box to replace previous monumentation and witnessed as shown below.

RATIFIED BY PEER GROUP
PA 345 OF 1997
MONROE COUNTY, MICHIGAN
date: 4/9/96
County Rep. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap in monument box and this position not established by original government surveyors and this monument is accepted as the best available evidence of the position of the corner and witnessed:

- monument box is +/- on centerline of pavement
South 80° West 29.95 feet reset nail & large shiner in northerly face of twin 12 inch tree
North 70° East 28.30 feet found nail/washer in southerly face of telephone pole
South 80° East 26.33 feet reset nail & large shiner in southwesterly face of 48 inch American Elm
South 35° East 28.20 feet in southerly end of 12 inch concrete culvert
South 40° West 40.2 feet to northeasterly face of 4" diameter PVC pipeline marker or test station

Signed by [Signature]
Surveyor's Michigan License No. 19474

Date 12/17/1996

lac / ref. 95-0025

