

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in SECTION
MONROE (58)
 (County)

Located In: FRENCHTOWN TWP. Corner Code # F-5
T 6 S R 9 E
 1. Public Land Survey S T R
 2. Property Controlling In Section S T R
 3. Miscellaneous Property in Sec. S T R
 4. Lot No. , Recorded Plat
 5. Private Claims

RECEIVED FOR RECORD
 99 DEC 28 AM 8:40
George B. Warnke
 REGISTER OF DEEDS
 MONROE COUNTY, MICH.

1998 & 1999 G.B. Warnke Private Remonumentation Corner

I, George B. Warnke, Jr., in a field survey on November, 1998 - do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 / GLO / Joseph Fletcher / West - On the true line between Secs. No. 9 & 16 - 40.00 - Set the 1/2 sec. post at average dis. from which an Elm 10 ins. dia. bears N46E 12 lks. dis. & a B. Oak 10 ins. dia. bears N24W 4 lks. dis. - 80.00 - Section corner 6/1951 / A.J. Marino / field notes / 30" Ash in corner / shows very old fence to south & east 1962 / R. Graf @ Michigan Dept. of Transportation / 1/2" Pipe / N03°E 37.35' 7" Apple & N40°W 43.45' 7" Ash & N80°W 54.89' 13" Ash Year? / Detroit Edison / witness cards / center of 36" Ash / westerly 2' Fd. Iron & easterly 4' Fd. Iron
- 1972 / Detroit Edison / Drawing #6MS1020-43 / Center of Tree / shows southerly 220.19' to CL of S. Stony Creek Road (17' Wd. Gravel)
- 1982 / Glenn R. Hobgood @ Michigan Dept. of Transportation / LCRC, Liber 2, Page 463 / Found 1/2" Pipe in N.W. Rod of 44" Stump. Fits reasonably close to distance from N.W. corner Sec. 16 according to 1962 Survey: 2624.25' measured from N.W. cor. Sec. 16 & 2625.41' record 1962 Survey / witnesses: N30°W 43.54' nail & tag W side 14" Ash & N35°E 51.50' nail & tag W side 46" Tamarack & N60°E 19.02' nail & tag S. side 16" Thornapple & West 2624.25' 3/4" pipe, N.W. cor. Sect. 16
- 1983 / George B. Warnke, Jr. / Job #83-58 / Center of 36" Dead Tree / Fd. 3/8" Iron Pipe 2.11' W. & 0.2' N. - witnesses to Iron N30°W 43.57' MSHD nail & shiner to SW face 13" tree & N45°E 18.97' MSHD nail & shiner to SE face 10" Hawthorne N30°E 51.48' MSHD nail & shiner to W. face of 44" Willow
- 5/1987 / Gregory Stephens #29252 @ Detroit Edison / Job #8704109 / Set Iron Pipe in Center of Tree Stump / 10/1994 / David Andrus @ J.C. Andrus / Job #94S-7380 / Fd pin is set in center of a dead tree stump. The tree was the N1/4 corner.
- 3/1995 / John Blanchard @ David Arthur Consultants / Job #94-D-227 / Found capped Iron DECO #29252 / N45°E 18.40' to existing PK nail in south face of 18" Thornapple & N10°W 46.50' to existing PK nail in N.W. face of 19" Maple tree West 36.80' to set PK nail in east face of 18" Maple tree & South 69.85' to set PK nail in north face of 24" Hickory tree

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner is located about 1/2 mile east of Monroe Street.
- 11/3/98 Found 1" Pipe & Cap No. 29252 at 6" out of ground / witnesses: N45°E 18.67' Fd MSHD nail/shiner S'ly face 18" Thornapple & N15°W 3.00' Fd. 1/2" Pipe 12" tall N10°W 46.50' Fd nail & reset double head nail / remon shiner S'ly face of 19" Maple (Boxelder) N35°E 50.00' set double head nail / remon shiner S'ly face 48" Shagg Bark tree (Tamarack?) East 4.35' set double head nail / remon shiner N'ly face 6" Boxelder Found 1/2" Pipe 12" tall (westerly iron) N47°E 18.90' Fd MSHD nail/shiner S face 18" Thornapple & S75°E 3.00' Fd 1" pipe & Cap No. 29252 N30°E 49.25' Set double head nail / remon shiner S'ly face 48" Shagg Bark tree (Tamarack?) N10°W 43.80' Fd nail & reset double head nail / remon shiner in S'ly face 19" Maple (Boxelder) East 7.0' set double head nail / remon shiner in N'ly face 6" Boxelder
- 11/25/98 - Set 1" x 36" pipe (1/2" pipe fd. 1.9' W'ly & 1" capped #29252 pipe fd. 2.1' S'ly).
- 8/99 - set brass remonumentation cap on 1" x 36" pipe.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 11/24/98, COUNTY REP. *[Signature]*

Corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1" x 36" pipe with brass remonumentation cap (1/2" pipe fd. 1.9' W'ly & 1" capped #29252 pipe fd. 2.1' S'ly) & Witnesses: North 45° East 17.50 feet to found MSHD nail / shiner in S. face 18" Thornapple North 30° East 48.45 feet to set double head nail / shiner (Remon) S'ly face of 48" Hickory North 10° West 44.72 feet to set double head nail / remon shiner in S'ly face of 19" Maple (Boxelder) South 85° East 5.62 feet to set double head nail / remon shiner in N'ly face of 6" Boxelder South 20.00 feet to set 5/8" x 30" rebar

Signed by *[Signature]*
 Surveyor's Michigan License No. 19474



Date November 5, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1994