



(Section A continued from reverse side)

- 1903 L.A. Howard survey shows "stone found" @ S.W. corner of Section 23.  
1929 Dr. Victor Newman survey shows "NE corner Section 27" (no material)  
1939 Angelo Marino field notes show "stone found" - witnesses: NE'ly 102.8' dug well meas. from center  
NE'ly 34.4' fence cor. SE'ly 41' fence cor. SW'ly 32' fence cor.  
1949 Angelo Marino field notes show "F. stone S.E. Cor Sec. 22" - witnesses:  
NE'ly 34.67' (fence) cor. post SE'ly 34.67' (fence) cor. post  
1953 Angelo Marino field notes show "F. stone N.W. cor. Frac. Sec. 26 &  
shows dimension S'ly down Mentel Road 828.70 to P. valve stem being over/in conc. culvert  
1956 Angelo Marino survey (#56-A-251) shows "stone N.W. Cor. Frac. Sec. 26"  
? Who set Bolt or Spike (assumed to be same point) ?  
1963 Angelo Marino field notes show "F. Spike" @ intersection of centerlines of Fix & Mentel Roads  
1971 Case & Fleck survey (#15194), recorded in Liber 641, Page 155, shows "NE Cor. Frac. Sec. 27"  
1973 Case & Fleck survey (#15194-A), recorded in Liber 644, Page 946, shows "F. Bolt - NE Cor. Frac. Sec. 27"  
1975 Angelo Marino field notes show "F. Bolt - NW cor. Sec. 26" - witnesses:  
N45°W 45.20' MBT Pole S40°E 44.90' D.E. Pole N45°E 35.45' Cor. post  
Angelo Marino field notes show "found 60P nail over 1' long bolt with square head - witnesses:  
NW'ly 45.30' nail in P. pole NE'ly 35.52' nail in corner post SW'ly 44.80' nail in pole  
1977 Angelo Marino field notes show "F. R.R. Spk."  
George Warnke survey (#77-49) shows "NE cor. Frac. Sec. 27 - I.P. - witnesses:  
N45°W 45.52' nail SW face of tel. pole N45°E 35.68' nail SE face of fence corner post  
S40°W 44.73' nail NW face of elec. pole  
1979 Detroit Edison, R. Peterson, witness card notes "Found bolt spike S.W. corner, Section 23" - witnesses:  
N45°W 45.33' P.K. in M.B.T pole N45°E 35.77' P.K. in fence post  
S45°W 44.72' P.K. in D.E. pole  
Detroit Edison witnesses card (not dated) shows "stone - SW corner Sec. 23" - witnesses:  
NE'ly 34.6' to fence corner SE'ly 34.6' to fence corner  
1987 Glenn Richard survey (for Detroit Edison, #8612301 & #SE 1323-2) & recorded LCRC, Liber 3, Page 24, which  
show SW. COR. SEC. 23 - FOUND 1" SQUARE HEADED BOLT - witnesses:  
N45°E 46.50' rerod N45°W 45.45' nail & washer tel. pole  
N50°W 106.45' 4" well casing S45°W 44.70' nail & disc elec. pole  
1988 George Warnke notes (88-367) show "SW Cor. Sec. 23 - S.I. Pipe over stone - Bolt 3.24' N & 4.93' W  
N55°E 106.40' well casting (6) N30°E 72.31' nail & shiner in SW cor. RR tie planter  
S45°W 45.65' PK nail in NW face elec. pole N45°W 51.12' nail & shiner in SW face tel. pole  
N50°W 112.58' hand water pump (centerline) N70°W 98.52' nail & shiner in S. face 24" tree  
J.C. Andrus & Associates survey shows "Found existing iron bolt at Northeast corner, Northeast quarter,  
Section 27"  
George Warnke survey (88-667) shows "Southwest corner Sec. 23 - Iron pipe over high point of stone" -  
witnesses: N55°E 106.40' rear face 6" well casing S45°W 45.65' PK nail NW face elec. pole  
N45°W 51.12' nail SW face tel. pole N50°W 112.58' center of hand well pump  
Fd. bolt 1' deep - 3.24' north & 4.93' west  
Found stone from 1949 & 50 surveys - very old surveys note stone  
1990 George Warnke survey (90-266) shows "Northwest corner Section 26 & Southwest corner, Section 23"  
Found 3/4" bent iron pipe over stone - found bolt 3.2'N & 4.9'W - witnesses match last 1988 Warnke survey  
George Warnke recorded LCRC, Liber 3, Page 117, to "Set 3/4" iron pipe bent over high point of stone" -  
witnesses match last 1988 Warnke survey  
1990 James Andrus survey (90S-5989) notes "found existing iron bolt at Northeast corner, Northeast quarter,  
Section 27"  
1991 James Andrus survey (91S6145) notes "found iron pipe at the northeast corner of the northeast quarter  
Section 27"  
1996 George Warnke survey (94-0089-2), recorded in Liber 1534, Page 0808, notes "nail & shiner (per stone found  
GBW survey No. 90-266) Mon Box 3.2' N., 4.9' W. - witnesses:  
N55E 106.40' c/l of steel well casing N70W 98.52' nail in S face dead 24" tree  
N50W 112.58' c/l well casing N45W 64.88' nail/shiner in NE face new tele pole  
George Warnke survey (96-0091) notes "found nail & shiner over stone -  
bolt in mon. box, 3.1' N., 4.8' W. - ref. LCRC, L.3, P.24 - witnesses match above survey (94-89)  
George Warnke notes show stone & mon box (see Section B for further information)

(Section B continued from reverse side)

Reference Corner / Not Section Corner / has been used as section corner

Found bolt / re-set after excavation on 10/7/1997 (monument box removed and used in area of stone & post)

Witnesses: N40°E 72.57' bolt on top of RR tie planter  
N70°W 92.91' fd. nail in S. face dead 24" tree  
S50°W 46.98' set nail/shiner in SE face new elec. pole  
N45°W 59.14' set nail/shiner in NE face new tel. pole