

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Monroe

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>6</u> XX S., R. <u>10</u> XX E.	<u>I-1, I-2, I-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Alfred V. McCann, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 18, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|--|--|
| <p>I-1, Sec. Cor. common to Sec's 2&3, T6S, R10E, Sec's 34&35, T5S, R10E, 1" pipe with brass cap. 5" below road surface. S85°30'E, 20.31', 18" Elm, spike. S50°30'W, 34.86', 2" steel road sign. S68°W, 83.13', 36" Elm, spike, West, 110.3' E. ed. conc. bridge (Recovered 9/18/79)</p> | <p>I-2, 1/4 Sec. Cor. betw. 2&3 3/4" iron pipe. 12' W. of road center line. N89°E, 34.92', "T" fence post, N42°30'W, 14.71', spike in fence post, N56°45'E, 87.67', SW cor. house foundation. (Recovered 9/18/79)</p> | <p>I-3, Sec. Cor. common to Sec's 2,3,10,&11. 4" conc. filled iron pipe with std. brass cap. East, 0.2', 2-1/2" leaning pipe. (Not Recovered)</p> |
|---|--|--|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

The described corners were located and re-monumented by W. L. Paddison, R.L.S., Michigan Department of Conservation in 1957-1958.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Alfred V. McCann CHIEF OF SURVEY PARTY DATE 8/18/80
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 13036