

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in MONROE (58) (County) Located In: BERLIN TWP. T6S R10E Corner Code # D-2
1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. Recorded Plat
5. Private Claims

RECEIVED FOR RECORD
99 DEC 29 AM 8:42
REGISTER OF DEEDS
MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

1998 & 1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on 1998 & September, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO did not set center of section.
4/1949 - A.J. Marino - field notes - F. Stone
12/1950 - A.J. Marino - field notes - Found Stone
3/1954 - A.J. Marino - field notes - Found Stone
6/1957 - A.J. Marino - field notes - Stone
4/1962 - A.J. Marino - field notes - F. Stone
10/1971 - A.J. Marino - field notes - F. Stone - northeasterly 87.00' P. pole & southeasterly 41.46' P. pole & westerly 24.69' 15" tree
9/1974 - A.J. Marino - field notes - F. Stone
1976 - Lillian M. Subdivision plat - Liber 14, Page 26 - goes by center but does not note
1978 - James Fish - LCRC, Liber 2, Page 290 - Found Stone - N50°W 30.29' 18" tree & N40°W 40.89' 16" tree & N30°W 71.58' P. pole & S45°E 55.84' P. pole
12/1978 - James Fish - Survey #642 - no material
4/1984 - George B. Warnke, Jr. - Survey #84-126 - Set 1/2" Iron Rod over Found Stone - N60°W 68.08' SW corner of house res. No. 8742 & N30°W 71.50' nail in NE face tel. pole & S30°E 55.00' Nail in SW face elec. & tel. pole & S45°W 67.90' NE corner of house - res. No. 8689
1987 - George B. Warnke, Jr. - Survey #87-317 - Found Rod over Stone
1/1989 - George B. Warnke, Jr. - Survey #89-01 - Fd. 1/2" I. Rod over Fd. Stone - 4 witnesses match 1994 GBW #84-126
6/1992 - George B. Warnke, Jr. - Survey #92-0221 - Fd. 3/4" x 30" iron rod - field crew spoke with neighbor who said stone was removed during road work and now sits by his driveway - S30°E 55.90' fd. nail/washer NE side util. pole & S45°W 67.90' NE cor. res. #8689 & N30°W 71.52' fd. nail/washer NE side tele. pole & N60°W 50.80' SE cor. res. #8677

Grid table with columns A-M and rows 1-13. A star symbol is located at the intersection of row 2 and column C.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located near west edge of concrete pavement of Bomiea Road about 855 feet north of Dixie Hwy - Only the east 2/3 of road is paved. 1992 - George B. Warnke, Jr. found 3/4" x 30" iron rod. Measurements & witnesses fit corner to say it was re-established at the location of the stone which can be traced before 1949. 9/27/99 - chipped some concrete away & placed yellow remonumentation cap over found 3/4" x 30" iron pin about 0.2' west of edge of concrete pavement. Top of rod is now about 4" below surface of concrete pavement. Mr. Warnke spoke with Melvin Liedel @ 8677 Bomiea Road & David Wyatt @ 8689 Bomiea Road. Both men stated that they felt the center should be several (5 foot +/-) to the east. Mr. Liedel told me his property was 200 feet deep. We found a pinch pipe at his southwest corner. He showed Mr. Warnke about where he thought it should be. He agreed. We measured 200.2 feet to the 3/4" pin & used as the center.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 12/8/1998, COUNTY REP. [Signature]

This corner position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set yellow plastic remonumentation cap on existing found 3/4" x 30" iron pin & Witnesses:
S30°E 55.90' fd. nail/washer NE side util. pole
S45°W 67.90' NE cor. res. #8689
N30°W 71.52' fd. nail/washer NE side tele. pole
N60°W 50.80' SE cor. res. #8677

Signed by [Signature]
Surveyor's Michigan License No. 19474



Date October 26, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1994