

**SURVEY &
REMONUMENTATION**

DEC 1 8 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
06 SEP -6 PM 1:48

For corners in **COMMISSION**
MONROE (58)
(County)

| Located In: | Corner Code #: |
|-------------------------|----------------|
| T _____ R _____ | _____ |
| T <u>7S</u> R <u>6E</u> | <u>K-12</u> |
| T _____ R _____ | _____ |
| T _____ R _____ | _____ |
| S _____ T _____ R _____ | _____ |
| S _____ T _____ R _____ | _____ |
| S _____ T _____ R _____ | _____ |
| S _____ T _____ R _____ | _____ |

John Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Corner Submitted by George B. Warnke, Jr., P.S.

I, **G.B. WARNKE, JR.**, in a field survey on 5/26/1995 & 1996, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner between Sections 35 & 36 / not on road - 1/2 mile south of Morocco Road
1819, G.L.O. Surveyor, Joseph Fletcher, set 1/4 section post and witnessed: B. Oak 11" N18°E 6.50 links;
1900, L.A. Howard set stone;
1904, L.A. Howard notes stone;
1973, L.C.R.C. (Liber 1, Page 367) by Max W. Walter notes set 3/4" X 30" iron pipe on N. side fence corner;
1990, J.C. Andrus (survey #90S-5897) states found existing iron pipe;
1993, J.C. Andrus (survey #93S-6908) does not call out what is at corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994, G.B. Warnke field crew found a 3/4" iron pipe on northerly side of 6' high steel fence post. A 5 foot diameter area was probed around pipe and no stone was found. Fences no longer remain, area was cleared by farmer. Found remains of stumps noted in 1973 L.C.R.C. (Liber 1, Page 367), witnesses and distances fit.
2/27/96, corner was approved by Remonumentation Peer Group (see further information in dossier).
8/1/1996, set 1" x 36" iron pipe with brass remonumentation cap to replace found 3/4" iron pipe and witnessed as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap to replace found 3/4" iron pipe and is accepted as the best available evidence of the position of the original corner and witnesses:
South 05° West 54.95 feet to set nail/shiner in northerly face of 30" Cottonwood tree
South 45° East 31.87 feet to set nail/shiner in northwesterly face 6" Catalpa
South 0.35 feet to centerline of steel fence post
North 45° West 29.68 feet to set nail/tag in southeasterly face of 8" Cherry

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN
date: 2/27/98
County Rep.: [Signature]

Signed by [Signature] Date 8 / 23 / 1996
Surveyor's Michigan License No. 19474

