

NOV 02 2000

RECEIVED FOR RECORD

97 OCT 31 PM 1:51

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

Heri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

For corners in

<u>Monroe</u>	Located In:	Corner Code #
(County)		
	IDA TWP.	
1. Public Land Survey	T <u>7S</u> R <u>7E</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Scott A. Warnke / M.C.R.C., in a field survey on September 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Monroe County Road Commission Corner

- A. Description of original monument and accessories and/or subsequent restoration:
 - 1820 G.L.O. surveyor, J. Wampler, set 1/2 mile Post; B.O. 14", S 69°E, 14 Links; B.O. 20", N 58°W, 69 Links.
 - 1889 Willis Baldwin found Stone. Used Stone to establish and Set the center of Section 31, T7S,R7E.
 - 1893 A.F. Winney found 1/4 Post; B.Oak 14", S 69° E, 14 Links; White Oak 3", S 86-1/2° E, 52 Links.
 - 1904 L.A. Howard found Stone in line with fence and in road.
 - 1949 Surveyor Unknown, Found Stone; West 52.8' to nearest fence post; On E & W fence line to West.
 - 1964 M.R. Fleck used this corner for Boundary survey. Type of monument not given on survey.
 - 1965 Monroe Co. Road Commission found Stone on 1/4 section line.
 - July 1972 A.J. Marino found Stone and placed Iron over stone; S 32° E, 78.75' to P.pole; West, 31.80' to P.pole; S 70° W, 45.50' to 6" Oak. Marino also found a P.K. nail 1.50' South and 0.20' East of Stone. Marino used the Stone.
 - Dec. 1973 M.R. Fleck set R.R. Spike 1.56' South of a found Stone; Witnesses to R.R. Spike: S 30° E, 77.25' to nail in Telephone pole; West, 32.10' to nail in power pole. S 55° W, 40.35 to SE corner of shed.
 - 1975 M.R. Fleck found R.R. Spike; witnesses are the same as Dec. 1973 survey.
 - 1979 G.B. Warnke found R.R. Spike; Witnesses: West, 32.10' to nail in S. face of elec. pole; S 30° E, 77.25' to nail in SW face of tel. pole; S 50° W, 38.35' to NE corner of shed.
 - 1980 G.B. Warnke used R.R. Spike.
 - 1988 J.C. Andrus found existing Iron Pin; No witnesses given.
 - 1990 J.C. Andrus found existing R.R. Spike; No witnesses given.
 - 1995 David A. Andrus found R.R. Spike; No witnesses given.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 - September 16, 1997 Found R.R. Spike at road surface. Excavated a 2'x2' hole. No evidence found below R.R. Spike. On North side of hole could tell that the area had been excavated before. Widened hole 1' to the North and found a Stone 1.45' North of the R.R. Spike and 2.5' below the Road. Pulled the Stone but did not find any evidence of the post.

10-14-97 Monroe County Peer Group accepted the R.R.spike as the best available evidence of the position of the original corner.
RATIFIED BY PEER GROUP, P.A.345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/14/97, COUNTY REP. *[Signature]*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - 1" x 36" Iron pipe with brass Remon. disk in monument box:
 - North, 2652.09' to (corner C-11) 1" x 36" iron pipe with brass Remon. disk in monument box.
 - N 16° E, 184.57' to nail & shiner in West face of telephone pole.
 - S 85° E, 32.96' to 1/2" capped Iron pipe.
 - S 20° E, 76.11' to nail & shiner in East face of telephone pole.
 - N 85° W, 32.18' to nail & shiner in North face of Power pole.
 - N 20° W, 170.61' to nail & shiner in East face of power pole.
 - S 30° W, 81.83' to "MAG" nail in East face of 12" pine tree.



Signed by Scott A. Warnke

Date 10-20-97

Surveyor's Michigan License No. 41913