

**SURVEY &  
REMONUMENTATION**

APR 28 1995

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN  
date: 10/4/1994  
County Rep.: [Signature]  
For corners in

**COMMISSION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD  
94 DEC 16 PM 3:26

*[Signature]*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

MONROE (County) Located In: IDA TWP. Corner Code #  

1. Public Land Survey	T <u>7</u> S R <u>7</u> E	<u>  </u> E-6
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
2. Property Controlling in Section	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
3. Miscellaneous Property in Sec.	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>

4. Lot No.   , Recorded Plat     
5. Private Claims   

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**1994 MONROE COUNTY REMONUMENTATION PROGRAM**  
Peer Group approved corner on 10/4/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 11/23/1994, 19  , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E-6, T7S, R7E, Ida Township, Monroe County - ID No. 58 1/4 Corner Common to Sections 16 and 17 ( Douglas Road being 1/2 mile south of Lulu Road - 6 inch stone over yellow sand )  
1820, G.L.O. Surveyor, Joseph Wampler, set quarter section post witnessed: B. Oak 18 (inch) S.41°W. 10 links & B. Oak 20 (inch) N.16°E. 9 links. 1903, L.A. Howard found stake partition survey of Section 17, T7S, R7E. 1956, A.J. Marino notes unable to find stone. 1961, A.J. Marino notes placed spike. 1968, A.J. Marino notes iron pipe buried with witnesses. 1977, G.B. Warnke recorded L.C.R.C., Liber 2, Page 220.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-6 - 9/1994, found 1/2 inch x 8 inch iron pipe over 3/4 inch x 15 inch pinch pipe. Dug 20 inch diameter x 24 inch deep hole in yellow sand, no stone found. Set 1 inch x 36 inch iron pipe, 1.84 feet west of straight line between section corners and witnessed as shown below. 11/23/1994, set brass remonumentation cap on 1 inch x 36 inch iron pipe and set monument box.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-6 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap inside monument box to replace 1/2 inch iron pipe and pinch pipe and is accepted as the best available evidence of the position of the original corner and Witnesses:  
North 80° West 140.38 feet to southwest corner of attached garage to res'd # 5298  
West 33 feet to found 1/2 inch iron pipe  
North 80° East 19.93 feet to double headed nail/shiner in west side of 24 inch Oak  
South 30° East 37.29 feet to double headed nail/shiner in west side of 18 inch Maple  
West 4.5 feet to centerline of pavement

Signed by [Signature] Date 11/23/1994  
Surveyor's Michigan License No. 19474

