

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

RATIFIED BY FIELD GROUP

REGISTERED SURVEYOR

9/20/1994  
*[Signature]*

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONROE  
 (County)

Located In: IDA TWP. Corner Code #7

- |                                    |              |              |            |
|------------------------------------|--------------|--------------|------------|
| 1. Public Land Survey              | T <u>7</u> S | R <u>7</u> E | <u>E-8</u> |
|                                    | T _____      | R _____      | _____      |
|                                    | T _____      | R _____      | _____      |
|                                    | T _____      | R _____      | _____      |
| 2. Property Controlling in Section | S _____      | T _____      | R _____    |
|                                    | S _____      | T _____      | R _____    |
| 3. Miscellaneous Property in Sec.  | S _____      | T _____      | R _____    |
|                                    | S _____      | T _____      | R _____    |

RECEIVED FOR RECORD  
 94 NOV 23 AM 10:30  
*[Signature]*  
 REGISTER OF DEEDS  
 MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims  
1994 MONROE COUNTY REMONUMENTATION PROGRAM  
Peer Group approved corner on 9/20/1994 per Act 345 of 1990.

I, G.B. WARNE, JR., in a field survey on 9/29/1994, 19 \_\_\_\_\_

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

**E-8, T7S, R7E, Ida Township, Monroe County - ID No. 58**  
 Section Corner Common to Sections 20 & 21 (Douglas Road - 4 inch stone on mixed sand)  
 1820, G.L.O. Surveyor, Joseph Wampler, set 1/4 post between Sections 20 & 21 - witnesses: B. Oak 7 inch S.49°W. 54 links & B. Oak 7 inch N.38°E. 50 links. 1957, A.J. Marino notes indicate iron. 1969, A.J. Marino notes show P.I. 1972, M.R. Fleck recorded survey, Liber 615, Page 6, notes FIP. 1975, M.R. Fleck survey #18991 notes FD. IRON & survey #19031, recorded in Liber 694, Page 321, notes FD. IRON ROD. 1977, M.R. Fleck survey #19698, recorded in Liber 735, Page 561, notes Fd. 3/4 rod. 1978, M.R. Fleck survey #20,096, recorded in Liber 770, Page 948, notes FIP. 1978, M.R. Fleck survey #20,374 notes Fd. I. Rod. 1990, Gordon MacCannon survey, recorded in Liber 1139, Page 0543, notes Fd. 1/2" Rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 - 9/15/1994, dug 24 inch x 30 inch deep hole and found 5/8 inch iron rod and found 10 inch x 12 inch stone at 15 inches deep and 0.7 feet south and 0.5 feet west of found iron rod. Removed stone, excavated and probed, no further evidence found. Older witnesses fit within 0.04 feet. Reset iron rod in bottom of hole and placed 1 inch x 36 inch iron pipe over rod and witnessed as shown below. 9/29/94, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap over reset 5/8 inch iron rod and is accepted as the best available evidence of the position of the original corner and Witnesses:  
 West 25.06 feet to nail/shiner in west face of electric pole  
 West 33.0 feet to iron pipe (#6193)  
 South 55° East 148.70 feet to northwest corner of res'd #6203 foundation  
 South 30° East 189.2 feet +/- to center west side of 10 inch Maple  
 Southerly 80.5 feet +/- to res'd #6203 northerly house line extended

Signed by *[Signature]* Date 9/29/1994  
 Surveyor's Michigan License No. 19474

3 Unit 382