

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC -9 PM 12:53

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 10-4-94
County Rep.: [Signature]

For corners in

MONROE

(County)

Located In: IDA TWP. Corner Code ##

- | | | | | | | | |
|------------------------------------|---|----------|---|-------|----------|-------|-------------|
| 1. Public Land Survey | T | <u>7</u> | S | R | <u>7</u> | E | <u>F-13</u> |
| | T | _____ | R | _____ | _____ | _____ | _____ |
| | T | _____ | R | _____ | _____ | _____ | _____ |
| | T | _____ | R | _____ | _____ | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ | _____ |
| | S | _____ | T | _____ | R | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ | _____ |
| | S | _____ | T | _____ | R | _____ | _____ |

[Signature]
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 10/4/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 11/11/1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

F-13, T7S, R7E, Ida Township, Monroe County - ID No. 58

South 1/4 Corner of Section 33 on Township line

(Rauch Road, 1/2 mile east of Douglas Road - 1-1/2 inch asphalt, 8 inch concrete, yellow sand)
1820, G.L.O. Surveyor, Joseph Wampler, set 1/4 Section post witnessed: B. Oak 9 inch South 84° East 104 links. 1959 M.R. Fleck surveyed "Sherwood Park Plat", Liber 12, Page 17. 1959 A.J. Marino notes "spk-cap by Fleck". 1960, A.J. Marino notes found valve. 1972, M.R. Fleck records found valve in concrete pavement, 0.52 feet west of east line "Sherwood Park Plat", Liber 12 of plats, Page 17. 1980's and 1990's, G.B. Warnke found and used valve.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 - 9/26/1994, found auto valve at surface. Dug hole 18 inch X 36 inch, found a harrow tooth spike 8 inches long, 10 inches deep found a stone 0.30 feet east of auto valve and harrow tooth spike. Found no post under stone. Set a 1 inch X 36 inch pipe inside monument box replacing spike and auto valve and witnessed as shown below. 11/11/1994, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap in monument box to replace spike and auto valve and is accepted as the best available evidence of the position of the original corner and

Witnesses:

North 25° West 103.59 feet to southeast corner of brick residence No. 2112

North 70° West 107.84 feet to southeast corner of brick wall

South 30° West 27.20 feet to nail in power pole

North 34.45 feet to nail/shiner in fence post

Signed by

[Signature]

Date

11/11/1994

Surveyor's Michigan License No.

19474

