

**SURVEY &
REMONUMENTATION**

DEC 07 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

94 OCT 12 PH 2:23

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 8/19/1994

County Rep.: [Signature]

For corners in

<u>MONROE</u> (County)	Located In:	Corner Code #
	IDA TWP.	
1. Public Land Survey	T <u>7</u> S R <u>7</u> E	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Keri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 8/9/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on 8/19/1994, 19_____,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-4, T7S, R7E, 1/4 Corner Common to Sections 9 & 10
(Jackman Road, 1/2 mile south of Albain - gravel over mixed clay & sand)
G.L.O. Surveyor Joseph Wampler in 1820 set quarter section post as witnessed W.Oak 30 inches West 80 links and W.Oak 34 inches N6°W 51 links. 1951, field notes indicate stone found. 1974, A.J. Marino field indicates a small stone found over stone and a railroad spike set beside small stone with iron rod 2 foot west. 1977, G.B. Warnke, recorded L.C.R.C., Liber 2, Page 201, to set 1 inch iron pipe over large stone being 1.3 foot deep and set small stone beside pipe, which has been used to present.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 - 8/1/1994 - Found 1 inch by 1 foot iron pipe over 7 inch granite stone over red granite stone being 17 inches deep. Found 1/2 inch iron pipe on south edge with several pieces of metal. Since high point was only 0.15 feet from south edge, G.B. Warnke drove 1 inch x 36 inch iron pipe at south edge with top centered over high point of granite in same position as 1 inch x 1 foot iron pipe and placed small stone south of pipe in bottom of hole. 8/19/1994, set brass remonumentation cap on 1 inch x 36 inch iron pipe.
Rewitnessed as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 - Set brass remonumentation cap on 1 inch x 36 inch iron pipe over stone and is accepted as the best available evidence of the position of the original corner and
Witnesses:
North 85° East 14.45 feet north end 12 inch CMP
South 60° East 66.32 feet found nail/shiner northeast face utility pole
South 65° East 20.37 feet south end 12 inch CMP
South 40° West 65.10 feet found nail/shiner north face electric pole



Signed by [Signature] Date 8/19/1994
Surveyor's Michigan License No. 19474