

**SURVEY &  
REMONUMENTATION**

DEC 07 1994

**COMMISSION**

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN

date: 8/9/94  
County Rep.: [Signature]

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
94 OCT 12 PM 2:24

*[Signature]*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

For corners in	<u>MONROE</u>	Located In:	Corner Code =#
	(County)		
		IDA TWP.	
1. Public Land Survey		T <u>7</u> S R <u>7</u> E	<u>G-5</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**1994 MONROE COUNTY REMONUMENTATION PROGRAM**

Peer Group approved corner on 8/9/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on AUGUST 19, 1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●						
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-5, T7S, R7E, Section Corner Common to Sections 9, 10, 15 & 16  
( Intersection of Jackman & Lulu Roads - tar & large chip )

G.L.O. Surveyor Joseph Wampler in 1820 set a post at corner of Sections 9, 10, 15 & 16 and witnessed W.Oak 15 inch N79°W 13 links. 1972, Case & Fleck Surveys, recorded in Liber 627, Page 660 & Liber 636, Page 189 & Liber 650, Page 488, notes a F.I.P. (found iron pipe). 1976, G.B. Warnke Survey, Job No. 76-193, notes railroad spike 0.3 foot deep & recorded in L.C.R.C., Liber 3, Page 134, to railroad spike. Railroad spike or boat spike is noted in other surveys to present. August of 1994, G.B. Warnke found stone under railroad spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 - 8/2/1994, Found railroad spike 1 inch below surface. Dug 16 inch by 2 foot deep hole and found granite stone 9 inches deep. The high point of stone was 0.20 foot west and 0.17 feet north of railroad spike. No further evidence found under or by stone. Set 1 inch x 36 inch black iron pipe, at high point of stone, in monument box to replace stone. 8/19/1994, set brass remonumentation cap on black iron pipe. Witnessed as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 - Set 1-inch x 36 inch black iron pipe with brass remonumentation cap inside monument box to replace stone and is accepted as the best available evidence of the position of the original corner and Witnesses:  
North 45° East 36.63 feet found PK nail in northwest face electric pole  
South 45° East 51.58 feet found nail/washer in west face electric pole  
South 60° West 53.31 feet found nail/washer in north face telephone pole  
North 50° West 41.90 feet southeast face 2 inch diameter metal sign post

Signed by [Signature]  
Surveyor's Michigan License No. 19474

Date AUGUST 19, 1994

