

**SURVEY &
REMONUMENTATION**

DEC 07 1994

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 8-23-94
County Rep.: [Signature]

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
94 OCT 12 PM 2:27

Leri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

For corners in

<u>MONROE</u> (County)	Located In:	Corner Code -#
	IDA TWP.	
1. Public Land Survey	T <u>7</u> S R <u>7</u> E	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 8/23/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on AUGUST 23, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-8, T7S, R7E, 1/4 Corner Common to Sections 21 & 22
(Jackman Road, 1/2 mile south of Ida Center Road - gravel)
G.L.O. Surveyor set quarter Section post and witnessed: B. Oak 16 inch North 37 West 1.48 links and B. Oak 9 inch South 87 East 1.95 links. July 1978, G.B. Warnke Survey No. 78-149 notes found old hub and set iron pipe. October 1985, G.B. Warnke Survey No. 85-341 notes iron pipe replaced wood stake found 1 foot +/- deep in 1978. January 1993, J.C. Andrus Survey No. 93S-6947 notes found GBW pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 - 8/22/1994 - Found 1/2 inch capped iron pipe 6 inches below surface and found wood stake 11 inches down, which was carved from branch or small tree and no information as to who had set stake. Set 1 inch x 36 inch black iron pipe in place of pipe and witnessed as shown below. 8/24/1994 - set brass remonumentation cap on 1 inch x 36 inch black iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 - Set 1 inch x 36 inch iron pipe with brass remonumentation cap in place of pipe and is accepted as the best available evidence of the position of the original corner and
Witnesses:
West 30.85 feet east face of wood post
North 15° East 149.62 feet found nail/coin west face of electric pole
South 15° East 162.84 feet found nail in west face of electric pole
North &/or South 2626.18 feet to section corners G-7 or G-9, T7S, R7E

Signed by [Signature] Date AUGUST 24 1994
Surveyor's Michigan License No. 19474

