

**SURVEY &
REMONUMENTATION**

DEC 07 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 OCT 12 PH 2:30

Teri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

RATIFIED BY PEER GROUP
PA 345 OF 1990
MONROE COUNTY, MICHIGAN

date: 8/9/94
County Rep.: [Signature]

For corners in

MONROE
(County)

Located In: Corner Code #

IDA TWP.

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>7</u> S R <u>7</u> E | G-11 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 MONROE COUNTY REMONUMENTATION PROGRAM

Peer Group approved corner on 8/9/1994 per Act 345 of 1990.

I, G.B. WARNKE, JR., in a field survey on AUGUST 22, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11, T7S, R7E, Section Corner Common to Sections 27, 28, 33 & 34

(Intersection of Jackman & Morocco Roads - asphalt)

1802, G.L.O. Surveyor, Joseph Wampler, set post corner of Sections 27, 28, 33 & 34 - witnesses: B. Oak 14 inch South 40 West 42 links & B. Oak 19 inch North 56 East 48 links. 1950, A.J. Marino field notes indicate a stone. 1960, Case & Fleck survey indicates found stone. May 1972, Case & Fleck survey recorded in Liber 624, Page 5, notes F.I.P. (found iron pipe). June 1972, Case & Fleck survey recorded in Liber 627, Page 654, notes stone. 1973, M. Freels survey recorded in Liber 644, Page 798, notes R.R. spike found. 1977, G.B. Warnke recorded L.C.R.C., Liber 2, Page 257, replaced R.R. spike with 1 inch iron pipe over found stone being approximately 1.5 feet deep). 1994, G.B. Warnke found 1 inch x 16 inch iron pipe over stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 8/5/1994 - Found 1 inch x 16 inch iron pipe next to 1/2 inch x 24 inch rebar. Found railroad spike on stone. Dug 16 inch diameter hole at and 18 inches deep found 12 inch x 8 inch x 6 inch granite stone, with a 1/2 inch rod x 12 inches long next to stone with end over high point of stone. Dug further to find, at 24 inches deep, two 6 inch x 12 inch x 2 inch cut sand stones and found, at 30 inches deep, a 14 inch x 6 inch x 6 inch granite stone. No further evidence found. Replaced found monumentation with 1 inch x 36 inch iron pipe inside monument box. On 8/22/1994, set brass remonumentation cap on iron pipe. Witnessed as shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 - Set 1 inch x 36 inch black iron pipe with brass remonumentation cap inside monument box and is accepted as a careful and faithful perpetuation of the position of the original corner and Witnesses:
South 55° East 72.91 feet set nail/shiner north face electric service pole
South 30° West 67.18 feet found PK nail northeast face electric pole
North 45° West 53.43 feet southeast corner of church foundation
North 40° East 43.31 feet found PK nail northwest face utility pole



Signed by [Signature]

Date AUGUST 22,

Surveyor's Michigan License No. 19474