

**SURVEY &  
REMONUMENTATION**

DEC 07 1994

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD  
94 OCT 12 PH 2:33

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN  
date: 8/9/1994  
County Rep.: [Signature]

*Heri Allen*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

|                                       |                           |                |
|---------------------------------------|---------------------------|----------------|
| MONROE<br>(County)                    | Located In:               | Corner Code =# |
|                                       | IDA TWP.                  |                |
| 1. Public Land Survey                 | T <u>7</u> S R <u>7</u> E | G-12           |
|                                       | T _____ R _____           | _____          |
|                                       | T _____ R _____           | _____          |
|                                       | T _____ R _____           | _____          |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____          |
|                                       | S _____ T _____ R _____   | _____          |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____          |
|                                       | S _____ T _____ R _____   | _____          |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
**1994 MONROE COUNTY REMONUMENTATION PROGRAM**  
Peer Group approved corner on 8/9/1994 per Act 345 of 1990.

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |


I, G.B. WARNKE, JR., in a field survey on AUGUST 22, 1994, 19\_\_\_\_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
G-12, T7S, R7E, 1/4 Corner Common to Sections 33 & 34  
( Jackman Road, 1/2 mile south of Morocco Road - 4 to 6 inches of gravel over sand )  
1820, G.L.O. Surveyor, Joseph Wampler, set 1/4 section post - witnesses: B. Oak 20 inch South 51 West 68 links & B. Oak 13 inch South 11 West 102 links. 1972, Case & Fleck notes stone per survey recorded in Liber 627, Page 654. 1973, G.B. Warnke notes found iron pin over high point of stone found approximately 1 foot deep per surveys recorded in Liber 650, Page 191 & Liber 654, Pages 682 & 683 & Liber 654, Page 854. 1973, M. Freels notes iron pin found recorded in Liber 644, Page 797 & 798. 1974, M. Fleck recorded L.C.R.C., Liber 1, Page 452, to iron rod bent over stone. 1977, G.B. Warnke found iron pin leaning over high point of stone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
G-12 - 8/6/1994 - Found 1/2 inch iron rod leaning over stone. Found remains of wood at 24 to 28 inches and post or stake more or less under iron pin over stone. Set old pin in hole and drove 1 inch x 36 inch iron pipe, top being 6 inches below gravel road, and placed stone against north edge of pipe with bottom up with a sharp point. Filled bottom 1 foot of hole with heavy stone and remainder with road gravel. Old witnesses fit within reason. 8/22/94, set brass remonumentation cap on 1 inch x 36 inch iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-12 - Set 1 inch x 36 inch black iron with brass remonumentation cap to replace rod over stone and is accepted as a careful and faithful perpetuation of the position of the original corner and Witnesses:  
West 2 foot to centerline of gravel road  
East 36.91 feet to found nail/shiner in southwest face of 8 inch Maple  
North 30° West 111.31 feet to found PK/shiner in East face of telephone pole  
North 45° East 46.93 feet to set nail/shiner in West face of 6 inch Walnut  
South 30° West 109.11 feet to found PK/shiner in East face of telephone pole



Signed by [Signature] Date 8/22/1994  
Surveyor's Michigan License No. 19474