

**SURVEY & REMONUMENTATION**

**FEB 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 NOV 12 PM 1:53

*Peri Allen*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

For corners in

MONROE (58)

(County)

Located In:

Corner Code #

1. Public Land Survey

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

IDA TWP.

T 7S R 7E K-7

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, G.B. WARNKE, JR., in a field survey on 1996-97, 19\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**1997 G.B. WARNKE CORNER**

Section Corner to Sections 13, 14, 23 & 24

At Geiger & Ida Center Roads being hard surface

A. Description of original monument and accessories and/or subsequent restoration:

1820, G.L.O. surveyor, Joseph Wampler, set post corner of Sec. No. 13, 14, 23 and 24, witnesses:  
Aspen 9 ins dia. bears N.41E. 8 lks. dis. & W. Oak 18 ins. dia. bears S.5W. 30 lks.

1972, Case & Fleck recorded survey (Liber 636, Page 177), set railroad spike with witnesses  
Case & Fleck recorded survey (Liber 636, Page 187), found spike with witnesses

A.J. Marino field notes, spike found

1973, A.J. Marino field notes, shows section corner but does not state what is at the corner

1982, Case & Fleck survey (#21065), found railroad spike with witnesses

1984, G.B. Warnke survey (#84-404), found railroad spike with witnesses

1987 & 1989, G.B. Warnke surveys (#83-132 & #89-313), found railroad spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996, G.B. Warnke survey (#91-0705 dated 7/2/96), found railroad spike per previous surveys in area and witnesses as shown below.

8/12/1997, Ratified by Peer Group, PA 345 of 1990, Monroe County, Michigan, County Rep. *[Signature]*

10/2/1997, set 1" x 36" iron pipe with brass remonumentation cap in monument box to replace found railroad spike.  
No other evidence found when excavating to replace railroad spike.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" iron pipe with brass remonumentation cap in monument box to replace found railroad spike and is accepted as the best available evidence of the position of the original corner. Witnesses:

South 40° East - 38.13 feet - found nail in northwest face telephone pole

North 50° West - 81.68 feet - found nail in southwest face electric pole

North 15° West - 43.40 feet - south end 12 inch culvert

North 30° East - 62.00 feet - found nail & shiner in southwest face telephone pole

Signed by

Surveyor's Michigan License No.

19474

Date

10/7/1997

