

MAY 2 1997

RECEIVED FROM SLD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Monroe</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>7E</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*David A. Andrus*  
REGISTER OF DEEDS  
MONROE COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Accepted by the Monroe County Remonumention  
Peer Group, September 24, 1996.

I, David A. Andrus, in a field survey on September 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Joseph Wampler set a post in 1820

Fleck found a pipe in 1973 and witnessed  
1974 Stanley in L.C.R.C. in Liber 2 Page 49 calls for pipe  
June 1996 David Andrus found pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found (2) 3/4 inch diameter pipes on top of  
each other. Set monument box and referenced  
location of pipes with (4) 2 foot o/s nails.  
Set 1 inch diameter pipe with brass plate in monument box

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set monument box with 1 inch diameter pipe with brass plate  
N 43° W 33.25' to P.K. southeasterly face guy pole  
N 45° W 47.26' to pin #27446  
S 45° W 29.95' to P.K. northeasterly face telephone and electric pole  
S 40° E 57.48' to northwest corner foundation of house

RATIFIED BY PEER GROUP  
PA 345 OF 1990  
MONROE COUNTY, MICHIGAN  
date: 9/24/1996  
County Rep: \_\_\_\_\_

Witnessed by *David A. Andrus* Date September 11, 1996  
Surveyor's Michigan License No. 40155