

RECORDATION

MAY 2 1987

RECORDATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED FOR FILE AND

97 FEB 21 PM 2:46

For corners in

Monroe (County)

Located In:

Corner Code #

- 1. Public Land Survey T 7S R 7E L-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Handwritten signature and stamp: REGISTER OF DEEDS, MONROE COUNTY, MICH.

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Accepted by the Monroe County Remonumentation Peer Group, September 24, 1996

I, David A. Andrus, in a field survey on September 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column M and row 11.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Joseph Wampler set a post in 1820 (GLO)

Fleck set a railroad spike (L.C.R.C. Liber 2 Page 13) (1973) on a line between (K-11) and (M-11) on the southerly projection of a fence on the north-south quarter line.

David Andrus found railroad spike and recorded L.C.R.C. Liber 4 Page 117 (June 1996)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike

Excavated and found no further monuments set monument box and (4) 2 foot o/s nails placed 1 inch pipe in monument box with brass plate

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1 inch pipe with brass plate in monument box S 45° W 39.65' to telephone and power pole N 55° W 31.27' to west end 12" concrete drain pipe North 18.77' to east end 12" concrete drain pipe S 70° W 64.18' to northwest corner concrete drive

RATIFIED BY PEER GROUP PA 345 OF 1990 MONROE COUNTY, MICHIGAN date: 9/24/1996 County Rep.:

Handwritten signature of David A. Andrus

Signed by Date September 24, 1996

Surveyor's Michigan License No. 40155