

RF

SEP 29 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in MONROE (58)  
(County)

Located In: LASALLE TWP. Corner Code # C-6

1. Public Land Survey T 7 S R 8 E

2. Property Controlling in Section  
S      T      R     

3. Miscellaneous Property in Sec.  
S      T      R     

4. Lot No.     , Recorded Plat     

5. Private Claims     

REGISTER OF DEEDS  
MONROE COUNTY, MICH

RECEIVED FOR RECORD  
99 SEP 30 AM 9:08

Register of Deeds Stamp & File Number

1998 & 1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on December, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 / GLO / Joseph Wampler / North - Between Secs. 17 & 18 40.00 - Set qr. Sec. post W. Oak 21 ins S71W 14 lks. & Hickory 7 ins S84E 14 lks.
- 1939 / A.J. Marino files (now George B. Warnke, Jr. files) / F. Stone / N. 147' N. side CL of S. Abut. Of bridge S45°E 43.5' Cor. Fence Post & S75°W 118' CL 20" Oak N45°W 40.5' Cor. Fence Post & N45°E 42.3' Cor. Fence Post
- 7/1968 / A.J. Marino / field notes / F.I. Rod in P & Seal Pvt. / northwesterly 49.7 T. pole northeasterly 40.2 Rd. sign southeasterly 44.0 P. pole #840
- 8/1972 / A.J. Marino / field notes / Iron Rod / northwesterly 49.90 T. pole (GBW note - close to AJM 1975 1<sup>st</sup> witness) northeasterly 99.29 T. pole southeasterly 44.19' P. pole (GBW note - close to AJM 1975 3<sup>rd</sup> witness) southwesterly 43.06 Stop sign post
- 5/1975 / A.J. Marino / field notes / F.I. Rod / northwesterly 49.95' T. pole & northeasterly 79.50' T. pole & southeasterly 44.20' P. pole
- 4/1979 / A.J. Marino / field notes / FIR / shows westerly 2824.88' measured to FIR at center Sec. 18
- 3/1983 / George B. Warnke, Jr. / LCRC, Liber 2, Page 475 / Found Iron Rod according to measurements from survey by A.J. Marino Jan. 12, 1960 - Found at centerlines of Strasburg & So. Otter Creek Roads. N45°W 49.92 Nail in east face of telephone pole & N20°E 124.94 Southeast corner of concrete wing-wall N65°E 79.11 Nail in north face of telephone pole & S45°E 44.13 Nail in north face of electric pole N88°29'30"E 2677.08 Found R.R. spike noted as center of Sec. 17 (A.J. Marino)
- 5/1983 / M.R. Fleck @ Case & Fleck / Survey #21141 / Found Iron
- 1988 / George B. Warnke, Jr. / LCRC, Liber 3, Page 61 / Found Iron Rod / N45°W (typed wrong as E) 49.91' PK nail in N.E. face tel. pole N20°E 99.35' Nail in N.W. face telephone pole (GBW note - close to AJM 1972 2<sup>nd</sup> witness) N70°E 79.05' Nail in N.W. face telephone pole (GBW note - close to AJM 1975 3<sup>rd</sup> witness & GBW 1983 3<sup>rd</sup> witness) S45°E 44.17' Nail in N. face electric pole (GBW note - close to AJM 1972 3<sup>rd</sup> witness & 1975 3<sup>rd</sup> witness & GBW 1983 4<sup>th</sup> witness)
- 1989 / George B. Warnke, Jr. / Survey #89-150 / Fd. I. Rod / witnesses match 1988 LCRC
- 1993 / George B. Warnke, Jr. / Survey #93-261 / Fd Iron Rod / reference LCRC, Lib. 3, Pg. 61

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located at intersection of S. Otter Creek Road (E-W) & Strasburg Road (N-S) in 1-1/2" tarby / 12" stone / sand / clay. 12/7/98 (TWC) found iron rod & checked witnesses from 1988 LCRC which were all good. 12/28/99 - (GBW) found 5/8" x 12" rod at surface at approximate centerline of pavement. Dug 20" diameter x 28" hole. Found evidence of excavation near northwest corner of a 15" to 18" diameter blue granite rock about 12-13" deep. Top of rod was over what appeared to be a 1" square hole toward south end of round top of stone. Broke up stone. No sign of GLO post at 24-26" deep. Set 1" x 36" pipe & brass remonumentation cap in vertical 4" clay tile (bottom 28"+/- deep). Set several pieces of stone on north side in deeper area. Third layer was totally around pipe. Set monument box flush with road.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 12/8/1998, COUNTY REP. [Signature]

and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1" x 36" pipe with brass remonumentation cap in 4" clay tile in set monument box to replace found rod & Witnesses:
- North 20° East 124.94' to southeast corner of concrete wing wall
- North 45° West 49.98' to found nail & washer in northwest face of telephone pole
- North 65° East 79.11' to nail & remon disc over nail & washer in northeast face telephone pole
- South 45° West 42.91' to set nail & remon disc in southeast face of electric pole (new)

Signed by [Signature]  
Surveyor's Michigan License No. 19474

Date AUG 5, 1999  
No. 19474  
STATE OF MICHIGAN  
GEORGE B. WARNKE, JR.  
PROFESSIONAL SURVEYOR  
RECEIVED MAY 14, 1975  
REVISED JAN. 1983  
REVISED OCT., 1994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

(13) C-6, T7S, R8E, LASALLE TWP.