

NOV 02 2000

RECEIVED FOR RECORD

97 OCT 31 PM 1:58

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1979

Peri Allen
REGISTER OF DEEDS
MONROE COUNTY, MICH

For corners in

Monroe
(County)

Located In: Corner Code #

Lasalle Twp.

T	<u>7S</u>	R	<u>8E</u>	<u>D-9</u>
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Scott A. Warnke / M.C.R.C., in a field survey on July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Monroe County Road Commission Corner

- A. Description of original monument and accessories and/or subsequent restoration:
 - 1820 G.L.O. Surveyor, Joseph Wampler, set post at the midway distance; B.O. 6", N 5° E, 11 links; B.O. 5", S 8° E, 37 links.
 - 1880? F.G. Buckley surveyed the E 1/2 of the SE 1/4; Found stone.
 - 1954 A.J. Marino found iron pin 0.3' deep. Witnesses: South, 24.62' to cap in fence post; SW, 51.8' to cap in fence post; NW, 46.6' to cap in fence post;
 - 1958 A.J. Marino found R.R. spike; witnesses not given.
 - 1969 Case & Fleck used for boundary survey in section 20. Material and witnesses of corner not given.
 - 1973 M.R. Fleck found R.R. spike; Witnesses: S 25° W, 101.75' to NE corner of frame tri-level; South, 80.10' to nail in 24" Oak; N 55° E, 49.70' to nail in telephone pole.
 - 1985 G.B. Warnke found R.R. spike used for location survey.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 - Excavated a 2' x 2' x 3' deep hole at location of R.R. Spike. Probed in hole with a 4' probe in all directions but did not hit anything. Set 1" x 36" Iron pipe with brass "Remon." disk in Monument box.
 - 10-14-97 Monroe County Peer Group accepted the R.R. spike as the best available evidence of the position of the original corner. RATIFIED BY PEER GROUP, P.A. 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/14/97, COUNTY REP. *[Signature]*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - 1" x 36" Iron pipe with brass "Remon." disk in monument box.
 - N 65° E, 50.54' to a "MAG" nail and M.C.R.C. tag in south face of telephone pole.
 - S 69° E, 174.53' to chiseled "+" in steamer cap of fire hydrant.
 - South, 28.50' to a nail and shiner in West face of power pole.
 - S 47° W, 116.19' to the NW corner of a block foundation of a porch to House # 2095.



Signed by Scott A. Warnke

Date 10-20-97

Surveyor's Michigan License No. 41913