

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

For corners in
MONROE (58)
(County)

Located In: Corner Code #

LASALLE TWP.

T 7 S R 8 E

E-7

- | | | | | |
|---------------------------------------|---|---|---|-------|
| 1. Public Land Survey | S | T | R | _____ |
| 2. Property Controlling in Section | S | T | R | _____ |
| 3. Miscellaneous Property in Sec. | S | T | R | _____ |
| 4. Lot No. _____, Recorded Plat _____ | S | T | R | _____ |
| 5. Private Claims _____ | | | | _____ |

REGISTER OF DEEDS
MONROE COUNTY, MICH.
Handwritten Signature

RECEIVED FOR RECORD
99 DEC 28 AM 8:43

1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on September, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in

Register of Deeds Stamp & File Number

conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 - GLO - Joseph Wampler - 80.00 / Set post corner of Secs. No. 16, 17, 20 & 21 from which a W. Oak 38 ins. dia. bears S30E 19 lks. dis. & a Hickory 18 ins. dia. bears East 22 lks. dis.
- 1972 - A.J. Marino notes - Found Spike - N45°W 43.05' to nail in power pole & S45°E 90.30' to N.W. cor. foundation & N45°E 41.05' to face of tele. pole
- 1972 - Gary Stanley - LCRC, Liber 1, Page 380 - Found Bolt - NW'ly 43.6 ft. to nail in power & telephone pole NE'ly 41.53 ft. to nail in power & telephone pole SE'ly 53.60 ft. to nail in 10" Maple
- 1974 - Case & Fleck - Survey #18692 - Liber 684, Page 699 - FD RR SPK - N45° E 44.54' to nail in P. Pole & N45° W 43.60' to nail in P. Pole & S40E 53.96' to nail in 8" Maple
- 1983 - GB Warnke - Survey #83-360 - RR Spike Found - S45°W 36.85 to CL Bell End 30" R.C.P. & S45°E 41.56 to Top Bolt Hydrant & N45°E 40.88 to Nail & Shiner Face T. Pole & N45°W 43.92 to Nail & Tag SW Face P. Pole
- 1988 - GB Warnke - Survey #88-134 - Found Railroad Spike - N45°E 41.04 PK nail SW face pole & N50°W 43.63 RR spike S. face pole & S45°E 41.59 top nut of hyd't & S45°W 36.27 punch hole in S. end 36" culvert
- 1989 - GB Warnke - Survey #88-485 - Found RR Spike - 4 witnesses match 1988 GBW 88-134
- year? - AJ Marino notes - FND. R.R. SPIKE - NE'ly 41.62' Nail in P.P. & SE'ly 41.65' CL Fire Hyd. & SE'ly 54.0' CL 6" Maple & SW'ly 36.90' CL 24" Conc. Cross Pipe & NW'ly 43.70' R.R. Spike in P.P.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located at Yargerville & Suder roads in 4" aspha.t over 1-1/2" tarby over stone.
9/99 - Dug 28" diameter hole. Found old R.R. spike about 5-1/2" deep - no other evidence found. Dug hole 30 to 32" deep still no stone. Set 1" x 30" rod in bottom of hole. Set 1" x 36" pipe with set brass remonumentation cap in set monument box to replace found RR spike.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/12/1999, COUNTY REP. *[Signature]*
Corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 36" pipe with set brass remonumentation cap in set monument box & Witnesses:
North 45° West 43.90 feet to set nail & remonumentation shiner in southwest face of electric pole
North 40° East 41.55 feet to used found PK nail in southeast face of utility pole
South 55° East 41.58 feet to top nut of hydrant
South 45° East 54.02 feet to set double head nail & remonumentation shiner in southwest face of 10" Maple
South 45° West 36.27 feet to drill hole near (top) south end 36" concrete culvert pipe
Drain runs north along west edge of gravel pavement of Suder Road
Section line is 4-5' east of west edge of pavement

Signed by *[Signature]*
Surveyor's Michigan License No. 19474



Date October 27, 1999