

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

REGISTER OF DEEDS
MONROE COUNTY, MICH
[Signature]

RECEIVED FOR RECORD
99 DEC 28 AM 8:45

For corners in MONROE (58)
Located In: LASALLE TWP.
Corner Code #: E-8
1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on September, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1820 - GLO - Joseph Wampler - 40.00 / Set the 1/2 mile post from which a W. Oak 10 ins. dia. bears N70W 8 lks. dis. & an Aspen 9 ins. dia. bears East 38 lks. dis.
year? - AJ Marino - notes - found I.R. bent over stone - W 35.09' nail in P.P. & ENE 29.0' CL 8" Walnut & ESE 45.22' nail in P.P. & SSE 136.75' nail in 12" Walnut
1973 - Melvin Fleck / Case & Fleck - LCRC, Liber 1, Page 323 - Found Stone Monument with TP. over top - SWly 35.60' SW to nail in P. Pole & S20°E 45.63' to 8" tree & East 28.90' to 8" tree
1983 - GB Warnke - Survey #83-360 - Iron over Stone - Easterly 33' to iron & East 38.90' to 10" tree & SE'ly 136.68' to nail w./s. tree & West 34.94' to nail N face of P. Pole
1988 - Gordon MacCammon - LCRC, Liber 3, Page 0045 - Fd. Stone Monument with 1/2" Iron Rod over top - 34.61' W to nail & shiner in power pole & 24.71' E to nail & shiner in corner post & 64.23' N35°E to nail & shiner in corner post

Grid table with columns A-M and rows 1-13. A star is marked at the intersection of column J and row 8.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner is located in Suder Avenue - 1/2 mile south of Yargeville Road in gravel pavement.
9/99 - Found 1/2" x 30" rod bent but twisted to NW - checked some witnesses but couldn't make work - rod was on east side - twisted to west & used point of stone. Set 1" x 36" pipe with set brass remonumentation cap in post hole 8" diameter - 36" deep filled with gravel to 24" depth. Found smaller stone at 36" depth but considered it incidental - broke through stone to drive the pipe. No post found. Position of LCRC witnesses were not very specific. Corner did not appear used recently - very compact stone & soil. Placed some clear glass around pipe at 24" deep +/- . Laid RR spike on south edge & 1/2" x 8" rebar on north edge 20" deep & set stone on south edge.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/12/1999, COUNTY REP.
Corner is accepted as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 1" x 36" pipe with brass remonumentation cap & Witnesses:
West 33.06 feet to found 3/8" iron rod
East 32.96 feet to found 3/8" iron rod
North 25° East 66.42 feet to set nail & remonumentation disc in west face of 15" Cottonwood - 2' above ground
East 41.39 feet to set nail & remonumentation disc in south face of 16" Walnut
South 10° East 136.75 feet to set nail & remonumentation disc in west face of 16" Walnut - used AJM measurement

Signed by [Signature]
Surveyor's Michigan License No. 19474



Date October 27, 1999