

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A., 1970

SECTION

For corners in MONROE (58)  
(County)

Located In: WHITEFORD TWP.  
T 8 S R 6 E

Corner Code # A-12

1. Public Land Survey \_\_\_\_\_  
 2. Property Controlling \_\_\_\_\_  
 in Section \_\_\_\_\_  
 3. Miscellaneous \_\_\_\_\_  
 Property in Sec. \_\_\_\_\_  
 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

REGISTER OF DEEDS  
 MONROE COUNTY, MICH.  
*Ken Allen*

RECEIVED FOR RECORD  
 99 DEC 28 AM 8:49

Register of Deeds Stamp & File Number

**1999 Remonumentation Program Corner**

I, George B. Warnke, Jr., in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**  
 Corner is COMMON to M-12, T8S, R5E, Lenawee County, which was established by GLO.  
 GLO did not set corner.

1820 - GLO - Joseph Wampler -  
 (A-13, T8S, R6E) 87.50 / Set post corner for Townships 8 & 9 South, Ranges 5 & 6 East from which an Ash 14 ins. dia. bears N79E 16 lks. dis. & a Cottonwood 19 ins. dia. bears S11E 20 lks. dis.  
 (A-11, T8S, R6E) 87.60 / Intersected Range line 27 lks. N. of the post / Set post corner of Secs. No. 30 & 31 from which a R. Oak 15 ins. dia. bears N89E 10 lks. dis. & a Lynn 10 ins. dia. bears S9W 9 lks. dis.

1976 - Glenn Richard - LCRC, Liber 2, Page 144 - Found 1-1/2" iron pipe which is common to Section 36, T8S R5E:  
 Boat spike in post West 32.33' & Steel post N35°E 31.10' &  
 Nail in T.P. S45°E 46.18' & Nail in T.P. N45°E 39.77'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner is located at County Line Road (N-S) & Lynch Road (E) in tarby pavement.  
 8/25/99 Found 1-1/4" I.D. l. pipe at surface. Dug hole 24" diameter x 24" depth. Top section of pipe 14-15" is broken at a coupling with 12-14" bottom section with maybe an iron inside could not break apart. Found pieces of granite on west side with a brick on north & south side. Drove pipe down. Poured old nails around pipe then placed stones & bricks back in place.  
 99 - Glenn Richard set Lenawee County Remonumentation cap on point.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/12/1999, COUNTY REP. *[Signature]*  
 This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 1/2" x 18" rebar in 1-1/4" I.D. pipe drove down about 14 inches deep with Lenawee County Remonumentation cap set inside set monument box & Witnesses:  
 South 85° West 14.95 feet to south edge of south post of arrow sign  
 West 25 feet to centerline of ditch of north & south  
 North 50° East 39.78 feet to found nail & shiner in southeast face of AT&T pole #299  
 South 45° East 46.30 feet to double head nail & shiner in southwest face of AT&T pole #300  
 North 20° East 89.40 feet to double head nail & remonumentation shiner in west face in 32" Sycamore

Signed by *[Signature]*  
 Surveyor's Michigan License No. 19474

Date November 11, 1999

