

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A., 1970

RECEIVED FOR RECORD
99 DEC 28 AM 8:50
REGISTER OF DEEDS
MONROE COUNTY, MICH

For corners in MONROE (58) Located in: WHITEFORD TWP. Corner Code # B-11
1. Public Land Survey T 8 S R 6 E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat S T R
5. Private Claims

Register of Deeds Stamp & File Number

1999 Remonumentation Program Corner

I, George B. Warnke, Jr., in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1820 - GLO - Joseph Wampler - 40.00 / Set the 1/2 mile post from which an Ash 8 ins. dia. bears S50W 4 lks dis. & a Lynn 10 ins. dia. bears S40E 9 lks. dis.
1973 - GB Wamke - Liber 647, Page 683 - Fd. stone 1.3 dp - set 3/4" i. pipe over - S30°W 17.6 cut "+" W. end S. H-wall & N5°W 9.89 Fd "+" cut E. End N. H-wall
1988 - Glenn Richard witnessed corner
1994 - GB Wamke - Survey 94-0107 - set 6" x 1" dome head RR bolt over found 3/4" i. pipe 6" deep - North 31.27' set nail/tag S face 6" walnut & N25W 25.80' cut "x" N end 54" conc. culvert & N75W 73.91' W end 8" steel culvert & S20W 26.20' cut "x" X end 54" conc. culvert

Grid table with columns A-M and rows 1-13. Cell (11, B) contains a small diagram of a monument.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner is located in Sterns Road (E-W) between County Line Road & Clark Road in 2" tarby pavement over stone over clay. 8/99 - Found 1" x 6" round top bolt over 3/4" x 14" pipe over stone at 22" deep. Stone 8" long x 4" x 3". Found 2-1/2" x 3/4" steel against south edge of stone. No post found. Set 1" x 36" iron pipe with brass remonumentation cap on RR spike. Laid old pipe & bolt at 32" & stone against north side with flat steel drove on southerly side of 1" pipe. Set monument box.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/12/1999, COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1" x 36" pipe with set brass remonumentation cap in set monument box & witnesses:
North 20° West 25.74 feet to "+" cut in top of concrete pipe at north end
South 20° West 26.18 feet to "+" cut in top of concrete pipe at south end
North 31.15 feet to south face 7" Walnut - nail grown over (see below)
North 05° East 31.47 feet to set double head nail & remon disc in west face of 7" Walnut
North 45° East 29.95 feet to east end of 8" CMP
North 70° West 73.91 feet to west end of 8" metal storm pipe

Signed by [Signature] Surveyor's Michigan License No. 19474



Date November 11, 1999