

**SURVEY &  
REMONUMENTATION**

**FEB 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A., 1970**

For corners in

MONROE (58)

(County)

Located In:

Corner Code #

**WHITEFORD TWP.**

1. Public Land Survey

T8S R6E

C-5

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

*Beni Allen*  
REGISTER OF DEEDS  
MONROE COUNTY, MICH

RECEIVED FOR RECORD  
97 DEC 30 PM 3:06

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**1997 Remonumentation Program Corner**

I, George B. Warnke, Jr., in a field survey on October 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			●										
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1820 GLO, Joseph Wampler, set post corner of Secs. 7, 8, 17 & 18 from which a Hickory 10 ins. dia. bears N34W 23 lks. dis. & an Ironwood 7 ins. dia. bears S11W 12 lks. dis.

1957 A.J. Marino notes – give 2 witnesses – no corner material

1979 Glenn R. Hobgood, LCRC, Liber 2, Page 313 & government witnesses card – NE. cor. Sec. 18 found large pointed stone on surface of ground. Set concrete monument with 5/8" rod 1 foot below surface, placed pointed stone on surface surrounded by stones.

1995? John Blanchard, David Arthur Consultants, survey – found 1" iron pipe.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

1997, G.B. Warnke found 4" concrete monument with 5/8" rod (per Hobgood). Also, found thick wall 3/4" ID pipe, which appears to fit John Blanchard information, located 0.60' North 74°17' East (being 0.16 feet North & 0.57 feet East). Found remains of cut off Elm 101 +/- north & measured 301' north from large stone (pointed) in a pile of stones 22' north of centerline of Head-O-Lake Road pavement.

RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 11/18/1997, COUNTY REP. *[Signature]*

12/1/1997, G.B. Warnke set brass remonumentation cap on found 5/8" rod in 4" concrete monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set brass remonumentation cap on found 5/8" rod in 4" concrete monument and is accepted as the best available evidence of the position of the original corner. Witnesses:

South 327.45 feet to 1" square bolt @ Head-O-Lake Road

South 01° East 329.81 feet to RR spike @ Head-O-Lake Road

North 71° West 275.36 feet to southwesterly fence corner

North 66° West to southeasterly fence corner

North 50° West to northeasterly fence corner

Reference Corner – North 74°17' East 0.60 feet to found thick wall 3/4" ID pipe, which appears to fit John Blanchard information

Signed by

*[Signature]*

Date 12/3/1997

Surveyor's Michigan License No.

19474



APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1  
REVISED MAY 14, 1  
REVISED JAN. 1  
REVISED OCT., 1