

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A., 1970**

For corners in SECTION  
MONROE (58)  
(County)

Located In: WHITEFORD TWP. Corner Code # C-11

T 8 S R 6 E

1. Public Land Survey S T R \_\_\_\_\_  
 2. Property Controlling in Section S T R \_\_\_\_\_  
 3. Miscellaneous Property in Sec. S T R \_\_\_\_\_  
 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD  
 99 DEC 28 AM 8: 51  
*Handwritten Signature*  
 REGISTER OF DEEDS  
 MONROE COUNTY, MICH

**1999 Remonumentation Program Corner**

Register of Deeds Stamp & File Number

I, George B. Warnke, Jr., in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and / or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1820 - GLO - Joseph Wampler - 80.00 / set post corner of Secs. 29, 30, 31 & 32 from which an Ash 16 ins. dia. bears N76E 25 lks. dis. & a Maple 8 ins. dia. bears N34W 15 lks. dis.
- 1886 - surveyor ? - from found stone at 1/4 post S. side / thence S89°W 38.14 to stone for corner sec. Found rotten roots where Maple & Ash should have been. Witness - Hick 8 N53W 58 - Maple 15 S31W 60
- 1973 - G.B. Warnke - Survey #73-6 recorded in Liber 647, Page 683 - Set I. Bolt over Stone 1.7 deep - N45°W 42.60 nail in guy pole & S45°E 42.88 nail in CP pole & N45°E 39.66 nail in tel. pole
- 1980 - Glenn Richard - LCRC, Liber 2, Page 407 - Found bolt with "x" cut on top 2" below the pavement surface - nail & disc in the following:  
 Tel. Pole N50°W 42.65' & Tel. Pole N45°E 39.70' & Elec. Pole S55°E 42.78'  
 Double headed nail & disc in Elec. Pole S70°W 114.42'
- 1994 - G.B. Warnke - Survey #94-0107 - Found I. Bolt Over Stone - N45W 42.60' nail in SW face guy pole & S45E 42.88' nail in SW face CP pole & N45E 39.37' nail in NW face tel. pole & S65W 114.42' nail / tag N face elec. pole
- ? - surveyor ? - witness card - Stone - S85°W 114.30 Power Pole & N.E. Road Sing 30.8

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner is located at Clark (N-S) & Sterns (E-W) roads in tarby pavement.  
 8/11/99 - found round top 3/4" x 15" bolt about 4" deep over a 4" x 7" round stone. Found 1-1/4" square stake 0.6 feet east. Seems to be another stone to southeast and northeast against stake. The stone was found in April of 1973 from witnesses on card at Monroe County Road Commission. We broke up stone under my bolt and set 3/4" x 15" threaded rod at 30". No post was found. Left the other stones in place. Put the pieces of broken up stone around base of 1" x 36" pipe set over the set rod. At about 18" deep, placed 2 bolts and railroad spike in triangle around the 1" set pipe. Set monument box at surface of pavement. 11/99 set brass cap on pipe.

**RATIFIED BY PEER GROUP, PA 345 OF 1990, MONROE COUNTY, MICHIGAN, DATE 10/12/1999, COUNTY REP.** *[Signature]*

Corner is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set 1" x 36" pipe with set brass remonumentation cap over set rod in set monument box & Witnesses:
- North 50° East 39.37 feet to set nail & remon. shiner in easterly face of telephone pole
- South 45° East 42.76 feet to found nail & shiner in southwest face in electric pole
- South 65° West 114.32 feet to set nail & remon. shiner above double head nail in north face electric pole
- North 45° West 42.60 feet to found nail & shiner in southwest face of guy pole about 2 foot north of centerline of pavement of Sterns Road

Signed by *[Signature]*  
 Surveyor's Michigan License No. 19474



Date November 24, 1999